

Interim Report

(Attachments)

December 26, 2011

Investigation Committee on the Accident at Fukushima Nuclear

Power Stations of Tokyo Electric Power Company

Table of contents

Attachment for Chapter II

Attachment II-1: Overview of reactor facilities at the Fukushima Dai-ichi NPS	1
Attachment II-2: Principle of power generation by boiling water reactor (BWR)	2
Attachment II-3: General layout of the Fukushima Dai-ichi NPS	4
Attachment II-4: Plant layout for Units 1 to 4 of the Fukushima Dai-ichi NPS	7
Attachment II-4: Plant layout for Units 5 and 6 of the Fukushima Dai-ichi NPS	10
Attachment II-5: TEPCO Organization Chart	13
Attachment II-6: TEPCO organization at the Fukushima Dai-ichi NPS	14
Attachment II-7: Shift arrangements at the Fukushima Dai-ichi NPS	15
Attachment II-8: Reactor system configuration at Unit 1 of the Fukushima Dai-ichi NPS	16
Attachment II-8: Reactor system configuration at Units 2 to 5 of the Fukushima Dai-ichi NPS	17
Attachment II-8: Reactor system configuration at Unit 6 of the Fukushima Dai-ichi NPS	18
Attachment II-9: Overview of damage caused by the Tohoku District - off the Pacific Ocean Earthquake and the ensuing tsunami (according to the latest information as of 16:00 December 1, 2011)	19
Attachment II-10: Earthquake and tsunami data from the Japan Meteorological Agency	20
Attachment II-11: Investigation results concerning the flooding of the Fukushima Dai-ichi NPS by the tsunami (level of inundation, water depth and flooded area)	27
Attachment II-12: Radiation dose in R/B, T/B, etc., and the location of facilities housed therein	28
Attachment II-13: Structures and components inside the reactor pressure vessel (Unit 1)	61
Attachment II-13: Structures and components inside the reactor pressure vessel (Units 2 to 5)	62
Attachment II-13: Structures and components inside the reactor pressure vessel (Unit 6)	63
Attachment II-14: Principle of measurement by reactor water level and reactor pressure instrumentation systems	64

Attachment II-15: Sectional lines are referred to from the preparation of sectional views of the reactor building and other facilities at Units 1 to 4 of the Fukushima Dai-ichi NPS	65
Attachment II-15: Sectional lines are referred to from the preparation of sectional views of the reactor building and other facilities at Units 5 and 6 of the Fukushima Dai-ichi NPS	66
Attachment II-15: Sectional view of the reactor building and other facilities at Unit 1 of the Fukushima Dai-ichi NPS	67
Attachment II-15: Sectional view of the reactor building and other facilities at Unit 2 of the Fukushima Dai-ichi NPS	68
Attachment II-15: Sectional view of the reactor building and other facilities at Unit 3 of the Fukushima Dai-ichi NPS	69
Attachment II-15: Sectional view of the reactor building and other facilities at Unit 4 of the Fukushima Dai-ichi NPS	70
Attachment II-15: Sectional view of the reactor building and other facilities at Unit 5 of the Fukushima Dai-ichi NPS	71
Attachment II-15: Sectional view of the reactor building and other facilities at Unit 6 of the Fukushima Dai-ichi NPS	72
Attachment II-16: Photographs showing damage to the Unit 1 reactor building	77
Attachment II-16: Photographs showing damage to the Unit 3 reactor building	79
Attachment II-16: Photographs showing damage to the Unit 4 reactor building	80
Attachment II-17: Isolation condenser (IC)	82
Attachment II-18: Reactor core isolation cooling (RCIC) system	83
Attachment II-19: High pressure coolant injection (HPCI) system	84
Attachment II-20: Photograph showing the overview of the seaside area and outdoor seawater facilities at the Fukushima Dai-ichi NPS	85
Attachment II-21: Damage to the emergency diesel generators (DGs), metal clad switchgear (M/C) and power centers (P/Cs)	86
Attachment II-21: Photographs showing damage to M/Cs and P/Cs	88
Attachment II-22: Illustration of damage to electrical installations inside and outside the premises of the Fukushima Dai-ichi NPS	89

Attachment II-23: Photographs showing damage to facilities required for the supply of external power	90
Attachment II-24: Fire protection system piping layout at the Fukushima Dai-ichi NPS	94
Attachment II-24: Fire protection system piping layout at the Fukushima Dai-ichi NPS (Units 1 to 4)	95
Attachment II-24: Fire protection system piping layout at the Fukushima Dai-ichi NPS (Units 5 and 6)	96
Attachment II-25: Location of the T/B water delivery ports at Units 1 to 4 of the Fukushima Dai-ichi NPS	97
Attachment II-25: Location of the T/B water delivery ports at Units 5 and 6 of the Fukushima Dai-ichi NPS	101
Attachment II-26: Photographs showing the installation of outdoor fire protection system facilities at the Fukushima Dai-ichi NPS	104
Attachment II-27: Photographs showing the installation of fire hydrants in the T/Bs of Units 1 to 3	108
Attachment II-28: Photographs showing damage to the main office building	111
Attachment II-29: Photographs showing damage to emergency access roads to the Fukushima Dai-ichi NPS	114
Attachment for Chapter IV	
Attachment IV-1: Layout of the Emergency Response Office	115
Attachment IV-2: Shift arrangements at the Fukushima Dai-ichi NPS	117
Attachment IV-3: Layout of the main control room for Units 1 and 2	118
Attachment IV-4: Isolation condenser (IC)	119
Attachment IV-5: Unit 1 reactor pressure	120
Attachment IV-6: Illustrated overview of the safety relief valve (SRV) operating principle (safety valve function)	121
Attachment IV-6: Illustrated overview of the safety relief valve (SRV) operating principle (in the case of relief valve actuation, ADS actuation or remote manual operation)	122
Attachment IV-7: Layout of the main control room for Units 3 and 4	123

Attachment IV-8: Unit 1 reactor water level	124
Attachment IV-9: Unit 1 reactor recirculation pump inlet temperature	125
Attachment IV-10: Illustrated overview of reactor core isolation by the IC system (closing of the isolation valve)	126
Attachment IV-11: The DG breaker ON/OFF status and IC operation status as recorded on the Unit 1 alarm typewriter	127
Attachment IV-12: Illustrated overview of reactor water levels	128
Attachment IV-13: Conceptual diagram of alternative water injection facilities (Unit 1)	129
Attachment IV-13: Conceptual diagram of alternative water injection facilities (Units 2 to 5)	130
Attachment IV-14: Overview of water injection by fire engines (at around 05:46 on March 12)	131
Attachment IV-15: Overview of water injection by fire engines (after around 10:52 on March 12)	132
Attachment IV-16: Examples of protective outfits and gear used	133
Attachment IV-17: Unit 1 vent line	134
Attachment IV-18: Illustrated overview of the operating principle of air-operated (AO) valves	135
Attachment IV-19: Overview of water injection by fire engines (at around 19:04 on March 12)	136
Attachment IV-20: Overview of water injection by fire engines (at around 7:00. on March 13)	137
Attachment IV-21: Overview of water injection by fire engines (at around 9:00. on March 13)	138
Attachment IV-22: Overview of water injection by fire engines (in the early evening of March 13)	139
Attachment IV-23: Overview of water injection by fire engines (until around 11:01 on March 14)	140
Attachment IV-24: Unit 2 vent line	141
Attachment IV-25: Unit 3 vent line	142
Attachment IV-26: Sectional view of the Unit 4 spent fuel pool and nearby facilities	143

Attachment IV-27: Overview of water injection by fire engines (at around 14:43 on March 14)	144
Attachment IV-28: Comparative review of the chosen methods for depressurization and alternative water injection of Unit2	145
Attachment IV-29: Overview of water injection by fire engines (after around 19:57 on March 14)	146
Attachment IV-30: Overview of water injection by fire engines (at around 20:30 on March 14)	147
Attachment IV-31: Pool gate configuration	148
Attachment IV-32: Progress in the cooling of spent fuel pools	149
Attachment IV-33: Water injection into the Unit 2 spent fuel pool using the FPC system	158
Attachment IV-34: Skimmer surge tank configuration	159
Attachment IV-35: Water injection into the spent fuel pools of Units 3 and 4 using the FPC system	160
Attachment IV-36: Alternative cooling system for the Unit 2 spent fuel pool	161
Attachment IV-37: Alternative cooling system for the Unit 3 spent fuel pool	162
Attachment IV-38: Water injection into the Unit 1 spent fuel pool using the FPC system	163
Attachment IV-39: Temporary SFP water injection system (“Mizuha”)	164
Attachment IV-40: Water injection into the Unit 4 spent fuel pool using the ICM tubes	165
Attachment IV-41: Alternative cooling system for the Unit 1 spent fuel pool	166
Attachment IV-42: Alternative cooling system for the Unit 4 spent fuel pool	167
Attachment IV-43: Cooling system for the Unit 5 spent fuel pool	168
Attachment IV-44: Cooling system for the Unit 6 spent fuel pool	169

Attachment for Chapter V

Attachment V-1: Geographical overview of the restricted area, deliberate evacuation areas, areas prepared for emergency evacuation and regions including specific spots from where evacuation is recommended (before the cancellation of areas prepared for emergency evacuation)	171
Attachment V-2: Geographical overview of the restricted area, deliberate evacuation areas, areas prepared for emergency evacuation and regions including specific spots from where evacuation is recommended (after the cancellation of areas prepared for emergency evacuation)	172
Attachment V-3: Overview of the penetration of groundwater into the basement of Unit 6 buildings	173
Attachment V-4: Photographs showing the penetration of water into the MC room (as of March 26)	174
Attachment V-5: Overview of the efforts to supply power from Unit 6 to Unit 5 (as of March 21)	175
Attachment V-6: Overview of water that remained in the second basement area of the Unit 6 R/B and RW/B	176
Attachment V-7: Configuration and layout of the subdrain system	177
Attachment V-8: Highly contaminated water outflow routes near the Unit 2 water intake (plane view)	178
Attachment V-9: Highly contaminated water outflow routes near the Unit 2 water intake (sketch)	179
Attachment V-10: Response to the outflow of highly contaminated water near the Unit 2 water intake (status at the time of detection)	180
Attachment V-11: Response to the outflow of highly contaminated water near the Unit 2 water intake (status after the injection of concrete)	181
Attachment V-12: Response to the outflow of highly contaminated water near the Unit 2 water intake (status after the injection of polymer, etc.)	182



Attachment V-13: Response to the outflow of highly contaminated water near the Unit 2 water intake (status after the injection of water glass-based chemical solution) - (1)	183
Attachment V-14: Response to the outflow of highly contaminated water near the Unit 2 water intake (status after the injection of water glass-based chemical solution) - (2)	184
Attachment V-15: Enhanced measures for preventing the spread of radioactive water (bird's eye view of the sites where measures were implemented)	185
Attachment V-16: Enhanced measures for preventing the spread of radioactive water (list)	186
Attachment V-17: Level of contaminated water in the Unit 3 T/B (in the pit)	187
Attachment V-18: Highly contaminated water outflow routes near the Unit 3 water intake (birds eye view)	188
Attachment V-19: Highly contaminated water outflow routes near the Unit 3 water intake (sketch)	189
Attachment V-20: Response to the outflow of highly contaminated water near the Unit 3 water intake	190
Attachment V-21: The International Nuclear and Radiological Event Scale ("INES") at nuclear facilities and installations	191
Attachment for Chapter VI	
Attachment VI-1: "Report on the results of the seismic response analysis of the reactor building and equipment, and piping systems, which are important for seismic safety, of the Fukushima Daiichi Nuclear Power Station Unit No.2, using the seismic records observed at the 2011 Tohoku District - off the Pacific Ocean Earthquake (Outline)" dated June 17, 2011 and prepared by Tokyo Electric Power Company (Abstract)	193
Attachment VI-2: "Report on the analysis of seismic records observed at the Onagawa Nuclear Power Station during the 2011 Tohoku District - off the Pacific Ocean Earthquake and the results of the tsunami survey (Outline)" dated April 7, 2011 and prepared by Tohoku Electric Power (Excerpt)	196

Attachment VI-3: “Summary of the analysis results of seismic records observed at the Onagawa Nuclear Power Station during The 2011 Tohoku District - off the Pacific Ocean Earthquake” dated April 7, 2011 and prepared by Tohoku Electric Power (Excerpt)	197
Attachment VI-4: “Report on the analysis and evaluation of earthquake seismic records observed at the Onagawa Nuclear Power Station during the 2011 Tohoku District - off the Pacific Ocean Earthquake and the assessment of the impacts on the equipment important for seismic safety (Outline)” dated July 28, 2011 and prepared by Tohoku Electric Power (Excerpt)	199
Attachment VI-5: Existing and newly introduced accident management measures (Unit 1)	201
Attachment VI-5: Existing and newly introduced accident management measures (Units 2 to 5)	202
Attachment VI-5: Existing and newly introduced accident management measures (Unit 6)	203
Attachment VI-6: Conceptual diagram of alternative water injection facilities (Unit 1)	204
Attachment VI-6: Conceptual diagram of alternative water injection facilities (Units 2 to 5)	205
Attachment VI-6: Conceptual diagram of alternative water injection facilities (Unit 6)	206
Attachment VI-7: Conceptual diagram of hardened vent system (Units 1 to 6)	207
Attachment VI-8: Conceptual diagram of the power supply interconnectivity (Units 1 to 6)	208
Attachment VI-9: Plot Plan of the Fukushima Dai-ichi NPS	209
Attachment VI-10: Plant layout for Units 1 to 4 of the Fukushima Dai-ichi NPS	212
Attachment VI-10: Plant layout for Units 5 and 6 of the Fukushima Dai-ichi NPS	216
Attachment VI-11: Accident management implementation organization	218
Attachment VI-12: Overview of the configuration of accident management procedures	219
Attachment VI-13: Method and frequency of accident management training programs	220

References

Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company: timeline of activities (2011)	221
Establishment of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company (cabinet decision on May 24, 2011)	222
Rules on the establishment of the Secretariat of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company (decision of the Prime Minister on May 31, 2011)	223
Structure of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company	224
List of experts (policy and technical investigation advisors) at the Secretariat of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company	225
Management procedures of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company (Decision of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company on June 7, 2011)	227
Information and informative materials to be handled without disclosure (Terms of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company on July 8, 2011)	229
Methods of Interview (Terms of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company on July 8, 2011)	231
List of English abbreviations	234

Overview of reactor facilities at the Fukushima Dai-ichi NPS

	Unit 1	Unit 2	Unit 3	Unit 4	Unit 5	Unit 6
Electric output (MWe)	460	784	784	784	784	1100
Thermal output (MWt)	1380	2381	2381	2381	2381	3293
Start of construction	Sep. 1967	May 1969	Oct. 1970	Sep. 1972	Dec. 1971	May 1973
Commissioning	Mar. 1971	Jul. 1974	Mar. 1976	Oct. 1978	Apr. 1978	Oct. 1979
Reactor type	BWR3	BWR4				BWR5
Reactor pressure vessel inside diameter (mm)	Approx. 4,800	Approx. 5,600	Approx. 5,570	Approx. 5,570	Approx. 5,570	Approx. 6,410
Reactor pressure vessel overall height (mm)	Approx. 20,000	Approx. 22,000	Approx. 22,000	Approx. 22,000	Approx. 22,000	Approx. 23,000
Reactor pressure vessel total weight (t)	Approx. 440	Approx. 500	Approx. 500	Approx. 500	Approx. 500	Approx. 750
Reactor pressure vessel design pressure (*1)	Approx. 8.62 MPa [gage] (87.9 kg/cm2 [gage])	Approx. 8.62 MPa [gage] (87.9 kg/cm2 [gage])	Approx. 8.62 MPa [gage] (87.9 kg/cm2 [gage])	Approx. 8.62 MPa [gage] (87.9 kg/cm2 [gage])	Approx. 8.62 MPa [gage] (87.9 kg/cm2 [gage])	Approx. 8.62 MPa [gage] (87.9 kg/cm2 [gage])
Reactor pressure vessel design temperature (C)	302	302	302	302	302	302
Number of fuel assemblies	400	548	548	548	548	764
Number of high burnup 8x8 fuels	68	-	-	-	-	-
Number of 9x9 fuels (type A)	-	-	516	-	-	-
Number of 9x9 fuels (type B)	332	548	-	548	548	764
Number of MOX fuels	-	-	32	-	-	-
Effective fuel rod length (m)	Approx. 3.66	Approx. 3.71	Approx. 3.71	Approx. 3.71	Approx. 3.71	Approx. 3.71
Number of control rods	97	137	137	137	137	185
Containment type	Mark I					Mark II
						
Containment overall height (m)	32	34	34.1	34.1	34.1	48.0
Containment diameter (m)	17.7 (sphere) 9.6 (cylinder)	20.0 (sphere) 10.9 (cylinder)	20.0 (sphere) 10.9 (cylinder)	20.0 (sphere) 10.9 (cylinder)	20.0 (sphere) 10.9 (cylinder)	25.9
Pool water volume in suppression chamber (m3)	1,750	2,980	2,980	2,980	2,980	3,200
Containment design pressure (*1)	Approx. 0.43 MPa [gage] (4.35 kg/cm2 [gage])	Approx. 0.38 MPa [gage] (3.92 kg/cm2 [gage])	Approx. 0.38 MPa [gage] (3.92 kg/cm2 [gage])	Approx. 0.38 MPa [gage] (3.92 kg/cm2 [gage])	Approx. 0.38 MPa [gage] (3.92 kg/cm2 [gage])	Approx. 0.28 MPa [gage] (2.85 kg/cm2 [gage])
Containment design temperature (C)	138 (D/W) 138 (S/C)	138 (D/W) 138 (S/C)	138 (D/W) 138 (S/C)	138 (D/W) 138 (S/C)	138 (D/W) 138 (S/C)	171 (D/W) 105 (S/C)
Spent fuel pool volume (% full core)	225	225	225	290	290	230
Spent fuel pool working temperature (C)	≤65	≤65	≤65	≤65	≤65	≤65
Spent fuel pool length (north-south: parallel to coastline) (m)	Approx. 7.2	Approx. 9.9	Approx. 9.9	Approx. 9.9	Approx. 9.9	Approx. 10.4
Spent fuel pool width (east-west: vertical to coastline) (m)	Approx. 12.0	Approx. 12.2	Approx. 12.2	Approx. 12.2	Approx. 12.2	Approx. 12.0
Spent fuel pool depth (deepest part) (m)	Approx. 11.8	Approx. 11.8	Approx. 11.8	Approx. 11.8	Approx. 11.8	Approx. 11.8
Spent fuel pool volume (m3)	Approx. 1,020	Approx. 1,424	Approx. 1,425	Approx. 1,425	Approx. 1,425	Approx. 1,497
Stockable number of spent fuels in pool	900	1,240	1,220	1,590	1,590	1,770
Number of spent fuels stored in pool (end of Dec. 2010)	292	587	514	1,331 (including 548 fuels extracted inside the reactor)	946	876
Number of new fuels stored in pool (end of Dec. 2010)	100	28	52	204	48	64

*1: The unit used in the application for the reactor establishment permit was kg/cm2 [gage].

Source: Tokyo Electric Power Company, "The impact of Tohoku-Chihou Taiheiyo-Oki Earthquake to Nuclear Reactor Facilities at Fukushima Dai-ichi Nuclear Power Station," September 2011

Principle of power generation by boiling water reactor (BWR)


“Based on the link from the ‘Disaster Prevention Network for Nuclear Environments’ created by the Nuclear Safety Division, Ministry of Education, Culture, Sports, Science and Technology”

(1) Principle of nuclear power generation

All power reactors existing in Japan are so-called light water reactors. Light water means normal water, and water is used in light water reactors in order to cool reactors when extracting thermal energy. Light water reactors are divided into boiling water reactors (BWRs) and pressurized water reactors (PWRs). As of the end of February 2011, fifty-four power reactors are in operation in Japan. In a BWR, steam produced inside the reactor directly rotates the turbine of the generator.

(2) Structure of boiling water reactor (BWR)

In a BWR, cooling water delivered by the feedwater pump and the recirculation pump flows along the fuel rods upward from the bottom of the reactor pressure vessel. Because the cooling water is heated by the fuel rods which are generating heat, the higher up it flows, the higher the water temperature becomes; it starts to boil along the way, emitting a mixture of water and steam upward. In a BWR whose electric output is comparable to 1,000,000 kW, the pressure of the cooling water is generally 7.0 MPa and the reactor exit stream temperature is 286 degrees Celsius in general. The steam separator located at the upper part of the reactor pressure vessel is to extract the steam from the boiling cooling water, and then, dry and deliver it to the turbine. The outline of a BWR nuclear power plant system is described in the figure below (the shape of the containment corresponds to that of Unit 6 in the Fukushima Daiichi Nuclear Power Station).



Based on 5-2, Graphical Flip-chart of “Nuclear & Energy Related Topics” 2011 by the Federation of Electric Power Companies of Japan



R/B	Reactor building
T/B	Turbine building
RW/B	Reactor waste treatment building
C/B	Control building
S/B	Service building
	Common auxiliary facilities (shared pool)
	Ultrahigh voltage switchyard
	Main office building
	Seismic isolation building

Attachment II-3

Based on data and documents by
Tokyo Electric Power Company

福島第一原子力発電所 配置図：General layout of the Fukushima Daiichi NPS

図上部 左⇒右

- ① 双葉町側：Futaba-machi
- ② 大熊町側：Okuma-machi
- ③ 取水路開渠：Intake channel open ditch
- ④ カーテンウォール：Curtain wall
- ⑤ 取水口：Water intake
- ⑥ 東波防堤：East breakwater
- ⑦ カーテンウォール：Curtain wall
- ⑧ 取水路開渠：Intake channel open ditch

図中央部 左⇒右

- ⑨ 超高压開閉所：Ultrahigh voltage switchyard
- ⑩ 66 kV 開閉所：66 kV switching station
- ⑪ 第 1 土捨場：1st Spoil bank
- ⑫ 固体廃棄物貯蔵所：Solid waste storage
- ⑬ 計測器予備品倉庫：Storage for measurement equipment and spare items
- ⑭ 定検用機材倉庫：Storage for regular inspection equipment
- ⑮ 物揚場：Shallow draft quay
- ⑯ 使用済燃料輸送容器保管建屋：Spent fuel transportation cask storage building
- ⑰ 駐車場：Parking space
- ⑱ 駐車場：Parking space
- ⑲ 事務本館：Main office building
- ⑳ 免震重要棟：Seismic isolation building
- ㉑ 駐車場：Parking space
- ㉒ 超高压開閉所：Ultrahigh voltage switchyard
- ㉓ 超高压開閉所：Ultrahigh voltage switchyard
- ㉔ 運用補助共用施設(共用プール)：Common auxiliary facilities (shared pool)
- ㉕ 放射性廃棄物集中処理施設：Centralized radioactive waste treatment facilities
- ㉖ 放射性廃棄物集中処理施設：Centralized radioactive waste treatment facilities
- ㉗ 排風気建屋：Air-exhaust ventilation building
- ㉘ 焼工建屋：Combustion building
- ㉙ 高放射性固体廃棄物処理建屋：High activity solid waste treatment building
- ㉚ 高温焼却建屋：High temperature incineration building

⑪ 共用サプレッションプールサージタンク建屋 : Common suppression pool surge tank building

⑫ 予備変電所 : Auxiliary substation

⑬ 用水池 : Reservoir

図下部 左⇒右

⑭ 双葉線 1 号・2 号 : Futaba Transmission Line, L1 and L2

⑮ 夜ノ森線 1 号・2 号 : Yornomori Transmission Line, L1 and L2

⑯ ろ過水タンク : Filtrate tank

⑰ 多目的運動場 : Multi-purpose athletic field

⑱ 登録センター : Registration center

⑲ 駐車場 : Parking space

⑳ 大熊線 1 号・2 号 : Okuma Transmission Line, L1 and L2

㉑ 大熊線 3 号・4 号 : Okuma Transmission Line, L3 and L4


㉒ 福島原子力技能訓練センター : Skills Training Center

㉓ 駐車場 : Parking space

㉔ 請負企業センター : Contractor center

㉕ サービスホール : Service hall

Plant layout for Units 1 to 4 of the Fukushima Dai-ichi NPS




Based on data and documents by
Tokyo Electric Power Company

Attachment II-4: Plant layout for Units 1 to 4 of the Fukushima Dai-ichi NPS

- ①物揚場：Shallow draft quay
- ②純水ポンプ建屋：Pure water pump building
- ③No.1 純水タンク：Deionized water tank 1
- ④No.2 純水タンク：Deionized water tank 2
- ⑤保健安全センター別館：Annex of the health and safety center
- ⑥薬品貯槽：Chemical storage
- ⑦厚生棟：Welfare building
- ⑧（旧）水処理建屋：(Former) Water treatment building
- ⑨事務本館別館：Annex of the main office building
- ⑩総合情報等：General information building
- ⑪飲料水タンク：Drinking water tank
- ⑫重油タンク：Heavy oil tank
- ⑬No.1 危険物倉庫：Dangerous object storage No. 1
- ⑭泡消火栓装置：Foam fire extinguishing equipment
- ⑮予備品倉庫：Spare item storage
- ⑯新サービス建屋：Units 1 and 2 new service building
- ⑰1 号機復水貯蔵タンク：Unit 1 condensate storage tank
- ⑱逆洗弁ピット：Reversing valve pit
- ⑲1 号機タービン建屋：Unit 1 turbine building
- ⑳起動変圧器：Startup transformer
- ㉑主変圧器：Main transformer
- ㉒地震観測小屋：Seismic observatory
- ㉓窒素供給装置：Nitrogen-supplying device
- ㉔1, 2 号機取水設備電源室：Power room for the water intake facility for Units 1 and 2
- ㉕機械室：Machine room
- ㉖No.1 軽油タンク：Light oil tank No. 1
- ㉗浄化槽：Septic tank
- ㉘2 号機復水貯蔵タンク：Unit 2 condensate storage tank
- ㉙1, 2 号機サービス建屋：Units 1 and 2 service building
- ㉚1, 2 号機サービスエリア：Units 1 and 2 service area
- ㉛1 号機コントロール建屋：Unit 1 control building
- ㉜2 号機コントロール建屋：Unit 2 control building
- ㉝1 号機廃棄物処理建屋：Unit 1 waste treatment building
- ㉞2 号機廃棄物処理建屋：Unit 2 waste treatment building
- ㉟1, 2 号機排気筒：Stack for Units 1 and 2

- ㉔ 1, 2 号機排気筒モニタ収納小屋 : Monitoring equipment chamber for Units 1 and 2 stack
- ㉕ 1, 2 号機超高压開閉所 Ultrahigh voltage switching station for Units 1 and 2
- ㉖ 1～4 号機共用所内ボイラ直流電源室 : DC power supply room for the common station-service boiler for Units 1-4
- ㉗ 所内変圧器 : Auxiliary transformer
- ㉘ No.2 危険物倉庫 : Dangerous object storage No.2
- ㉙ 1～4 号機発電機注入用窒素ガスボンベ室 : Nitrogen gas cylinder room for Units 1 to 4 generators
- ㉚ No.2 軽油タンク Light oil tank No.2
- ㉛ 3 号機復水貯蔵タンク : Unit 3 condensate storage tank
- ㉜ 立坑 : Shaft
- ㉝ メタクラ 2 S A 建屋 : Metal clad switch gear 2SA building
- ㉞ 3 号機原子炉建屋 : Unit 3 reactor building
- ㉟ 1, 2 号機活性炭ホールドアップ装置建屋 : Units 1 and 2 charcoal building
- ㊱ 3 号機活性炭ホールドアップ装置建屋 : Unit 3 charcoal building
- ㊲ 4 号機スクリーン電源室 : Power room of Unit 4 screen
- ㊳ 北側立坑 : North shaft
- ㊴ 3 号機主発電機励磁装置盤建屋 : Building for the energizing device of Unit 3 main generator
- ㊵ 励磁電源変圧器 : Energizing power transformer
- ㊶ 汚損検出器 : Contamination detector
- ㊷ 計算機室冷凍機 : Computer room cooler
- ㊸ タービン建屋換気系排気筒 : Stack for the turbine building ventilation system
- ㊹ 排風気建屋 : Air-exhaust ventilation building
- ㊺ 可燃性雑固体廃棄物焼却設備及び工作機械室（焼工建屋） : Miscellaneous flammable solid waste combustor and engineering machine room (combustion room)
- ㊻ 放射性廃棄物集中処理施設（プロセス補助建屋） : Central radioactive waste treatment facilities (auxiliary processing building)
- ㊼ 放射性廃棄物集中処理施設（プロセス主建屋） : Central radioactive waste treatment facilities (main processing building)
- ㊽ 高放射線性固体廃棄物処理建屋（サイトバンカー） : High activity waste treatment building (side bunker)
- ㊾ 高温焼却建屋 : High temperature incineration building
- ㊿ 共用サブプレッションプールサージタンク建屋 : Common suppression pool surge tank building
- ㊰ 軽油移送ポンプ : Light oil transfer pump
- ㊱ 水素トレーラー : Hydrogen trailer
- ㊲ 液体酸素タンク : Liquid oxygen tank

Plant layout for Units 5 and 6 of the Fukushima Dai-ichi NPS



福島第一原子力発電所 5号機及び6号機 配置図 : Plant layout for Units 5 and 6 of the Fukushima Dai-ichi NPS

図上部 左⇒右

- ① 5 / 6号機サンプリング建屋 : Units 5 and 6 sampling building
- ② 取水口 : Water intake
- ③ 循環水ポンプ : Circulating water pump
- ④ 5, 6号機取水設備電源室 : Power room for Units 5 and 6 intake facilities
- ⑤ 取水口 : Water intake
- ⑥ 循環水ポンプ : Circulating water pump
- ⑦ 重油タンク : Heavy oil tanks
- ⑧ サプレッションプール水タンク : Suppression pool water tank

図中央部 左⇒右


- ⑨ No. 6 軽油タンク : Light oil tank No. 6
- ⑩ 6号機ディーゼル発電機建屋 : Unit 6 diesel generator building
- ⑪ 6号機MGセット建屋 : Unit 6 MG set building
- ⑫ 6号機タービン建屋 : Unit 6 turbine building
- ⑬ 5, 6号機サービス建屋 : Units 5 and 6 service building
- ⑭ No. 3 軽油タンク : Light oil tank No. 3
- ⑮ 復水貯蔵タンク : Condensate storage tank
- ⑯ サービスエリア : Service area
- ⑰ 5号機タービン建屋 : Unit 5 turbine building
- ⑱ 5, 6号機コントロール建屋 : Units 5 and 6 control building
- ⑲ 6号機所内変圧器 : Unit 6 auxiliary transformers
- ⑳ 6号機主変圧器 : Unit 6 main transformer
- ㉑ 6号機復水貯蔵タンク : Unit 6 condensate storage tank
- ㉒ 電気品室 : Electrical item room
- ㉓ 非常用ディーゼル発電機室 : Emergency diesel generator room
- ㉔ 6号機原子炉建屋 : Unit 6 reactor building
- ㉕ 長期地震観測建屋 : Long-term seismic observation building
- ㉖ 5 / 6号機廃棄物地下貯蔵設備建屋 : Units 5 and 6 filter sludge tank room
- ㉗ 5号機起動変圧器 : Unit 5 startup transformers
- ㉘ 6号機雑固体処理建屋 : Unit 6 miscellaneous solid treatment building
- ㉙ 連絡通路 : Passageway
- ㉚ 廃棄物処理エリア : Waste treatment area

- ㊸主排気ダクト：Main exhaust air duct
- ㊹排気筒：Stack
- ㊺5，6号機排気筒モニタ収納小屋：Monitoring equipment chamber for the stack of Units 5 and 6
- ㊻5号機廃棄物処理建屋：Unit 5 waste treatment building
- ㊼5号所内ボイラー建屋：Unit 5 auxiliary boiler building
- ㊽5号機原子炉建屋：Unit 5 reactor building
- ㊾窒素供給装置：Nitrogen-supplying device
- ㊿主変圧器：Main transformer
- ㊽㊸励磁変圧器：Energizing transformer
- ㊽㊹所内変圧器：Auxiliary transformers
- ㊽㊺水素供給設備制御盤室：Hydrogen-supplying facility control board room
- ㊽㊻水素トレーラー：Hydrogen trailer
- ㊽㊼純水タンク：Demineralized water tank
- ㊽㊽N o . 4 資材倉庫：Material storage No.4

図下部 左⇒右

- ㊽㊽6号機超高圧開閉所：Ultrahigh voltage switching station for Unit 6
- ㊽㊼5号機超高圧開閉所：Ultrahigh voltage switching station for Unit 5
- ㊽㊽66KV開閉所：66kv switching station

TEPCO Organization Chart




*1 (Fukushima Daiichi, Kashiwazaki-Kariwa): Daiichi Operation Management Dept., Daini Operation Management Dept. (Fukushima Daini); Operation Management Dept. (Fukushima Daini); Maintenance Dept. (Fukushima Daini); Maintenance Dept. (Fukushima Daini); Maintenance Dept. (Fukushima Daini).
 *2 (Fukushima Daiichi, Kashiwazaki-Kariwa): Daiichi Maintenance Dept., Daini Maintenance Dept. (Fukushima Daini); Maintenance Dept. (Fukushima Daini).
 NOTE: The following organizations belong to TEPCO in addition to those indicated in this chart: [Branches] Switchyards (Saitama, Gunma).

Created by Tokyo Electric Power Company

TEPCO organization at the Fukushima Dai-ichi NPS


[At normal times]



[In a First Level Emergency] (after warning of an event specified in Article 10 of the Act on Special Measures concerning Nuclear Emergency Preparedness)

[In a Second Level Emergency] (after the occurrence of a situation specified in Section 1, Article 15 of the abovementioned Act)


As of February 1, 2011



Based on data and documents by Tokyo Electric Power Company


Attachment
II-6

Shift arrangements at the Fukushima Dai-ichi NPS




*1 One dedicated senior operator and main equipment shift operator are assigned to each plant.
*2 The number of operation shift team members may change depending on the circumstances at the relevant plant.

Based on the “Third Report on Regular Safety Review of the Fukushima Dai-ichi Nuclear Power Station Unit No.1” (November 2010) by Tokyo Electric Power Company




Reactor system configuration at Unit 1 of the Fukushima Dai-ichi NPS

Source: Tokyo Electric Power Company, "Report on Accident Management Preparation at the Fukushima Dai-ichi Nuclear Power Station," May 2002



Reactor system configuration at Units 2 to 5 of the Fukushima Dai-ichi NPS

Source: Tokyo Electric Power Company, "Report on Accident Management Preparation at the Fukushima Dai-ichi Nuclear Power Station," May 2002



Reactor system configuration at Unit 6 of the Fukushima Dai-ichi NPS

Source: Tokyo Electric Power Company, "Report on Accident Management Preparation at the Fukushima Dai-ichi Nuclear Power Station," May 2002

Prefecture	Personnel damage (number of persons)			Property damage (number of buildings)								
	Killed	Missing	Injured	Complete collapse	Partial collapse	Swept out	Total burn down	Partial burn down	Inundated above floor level	Inundated below floor level	Partial damage	Non-dwelling houses
Hokkaido	1		3		4				329	545	7	469
Aomori	3	1	61	311	853						121	1,194
Iwate	4,665	1,409	188	20,184	4,551		15		1,761	323	7,291	4,148
Miyagi	9,504	1,913	4,013	78,451	100,663		135		7,053	11,009	190,971	27,819
Akita			12								3	3
Yamagata	2		29	37	80							
Fukushima	1,605	221	241	18,432	57,850		77	3	62	339	133,492	1,071
Tokyo	7		90		11		3				257	20
Ibaraki	24	1	707	3,203	23,247		31		1,609	722	162,918	12,465
Tochigi	4		132	265	2,042						67,604	295
Gunma	1		38		7						16,154	195
Saitama			42	22	193		1	1		1	1,800	33
Chiba	20	2	251	783	9,221		15		153	720	34,237	660
Kanagawa	4		132		38						405	24
Niigata			3								9	7
Yamanashi			2								4	
Nagano			1									
Shizuoka			4							7	4	
Mie			1						2			9
Tokushima									2	9		
Kochi			1						2	8		
Total	15,840	3,547	5,951	121,688	198,760		281		10,973	13,683	615,277	48,412

Overview of damage caused by the Tohoku District - off the Pacific Ocean Earthquake and the ensuing tsunami (according to the latest information as of 16:00, December 1, 2011)

Based on the document (as of December 1, 2011) by the Emergency Disaster Countermeasures Headquarters, National Police Agency of Japan

Earthquake and tsunami data from the Japan Meteorological Agency

Date	Time	Information on hypocenter, magnitude, seismic intensity, tsunami, etc.		
		Hypocenter	Magnitude	Seismic intensity (Futabamachi, Fukushima)
March 11	14:46	Off the coast of Sanriku	9.0	Intensity 6 upper
	14:49	"Major tsunami warnings" were issued. (Fukushima Prefecture)		
	14:50	"The estimated arrival time of the tsunami" was announced as "15:10 with a projected height of 3 m		
	14:51	Off the coast of Fukushima Prefecture	6.8	4
	14:54	Off the coast of Fukushima Prefecture	5.8	4
	14:55	Off the coast of Ibaraki Prefecture	5.8	3
	14:58	Off the coast of Fukushima Prefecture	6.4	4
	(14:--)*	1.2 m backwash was observed in Soma point, Fukushima Prefecture.		
	15:05	Off the coast of Fukushima Prefecture	5.9	4
	15:06	Off the coast of Iwate Prefecture	6.4	3
	15:11	Northern Ibaraki Prefecture	5.6	2
	15:12	Off the coast of Fukushima Prefecture	6.1	4
	15:14	The announcement was made that "a tsunami arrived at the estimated arrival time with a projected height of 6 meters." (Fukushima Prefecture).		
	15:15	Off the coast of Ibaraki Prefecture	7.7	4
	15:25	Off the coast of Sanriku	7.5	3
	15:29	Off the coast of Sanriku	6.8	2
	15:31	The announcement was made that "a tsunami arrived at the estimated arrival time with a projected height of 10 meters." (Fukushima Prefecture)		
	15:38	Off the coast of Ibaraki Prefecture	5.5	2
	15:40	Off the coast of Iwate Prefecture	5.7	2
	15:44	Off the coast of Miyagi Prefecture	5.3	2
	15:46	Off the coast of Miyagi Prefecture	5.6	2
	15:48	Off the coast of Miyagi Prefecture	5.4	2
	15:49	Off the coast of Iwate Prefecture	5.8	2
	15:51	A tsunami water level of 9.3 m or higher was observed in Soma point, Fukushima Prefecture. (Announced by the Japan Meteorological Agency on April 13.)		
	15:57	Off the coast of Ibaraki Prefecture	6.1	3
	15:59	Off the coast of Fukushima Prefecture	6.7	2
	16:04	Off the coast of Miyagi Prefecture	5.8	2
	16:10	Off the coast of Fukushima Prefecture	6.0	2
	16:14	Off the coast of Ibaraki Prefecture	6.7	3
	16:16	Off the coast of Fukushima Prefecture	5.4	3
	16:22	Off the coast of Fukushima Prefecture	4.4	1
	16:25	Off the coast of Sanriku	6.4	2
	16:29	Off the coast of Iwate Prefecture	6.5	Intensity 5 lower
	16:34	Off the coast of Miyagi Prefecture	6.2	2
	16:36	Off the coast of Miyagi Prefecture	5.0	1

Date	Time	Information on hypocenter, magnitude, seismic intensity, tsunami, etc.		
		Hypocenter	Magnitude	Seismic intensity (Futabamachi, Fukushima)
March 11	16:40	Off the coast of Miyagi Prefecture	5.5	1
	16:54	Off the coast of Fukushima Prefecture	5.5	3
	17:05	Off the coast of Fukushima Prefecture	5.8	3
	17:12	Off the coast of Ibaraki Prefecture	6.6	3
	17:19	Off the coast of Ibaraki Prefecture	6.8	3
	17:31	Off the coast of Fukushima Prefecture	5.9	4
	17:35	Off the coast of Ibaraki Prefecture	5.2	2
	17:40	Off the coast of Fukushima Prefecture	6.1	4
	17:47	Off the coast of Fukushima Prefecture	6.0	2
	17:54	Off the coast of Fukushima Prefecture	4.8	1
	18:04	Off the coast of Ibaraki Prefecture	5.4	2
	18:15	Off the coast of Fukushima Prefecture	4.8	2
	18:19	Off the coast of Ibaraki Prefecture	5.0	1
	18:27	Off the coast of Miyagi Prefecture	5.3	2
	18:34	Off the coast of Fukushima Prefecture	4.8	2
	18:37	Off the coast of Ibaraki Prefecture	5.4	1
	18:42	Off the coast of Sanriku	5.6	1
	18:47	Off the coast of Sanriku	5.7	1
	18:52	Off the coast of Fukushima Prefecture	4.8	3
	18:55	Off the coast of Ibaraki Prefecture	5.3	2
	18:57	Off the coast of Ibaraki Prefecture	4.7	1
	18:59	Off the coast of Fukushima Prefecture	5.0	1
	19:10	Off the coast of Iwate Prefecture	6.2	2
	19:13	Off the coast of Miyagi Prefecture	5.3	1
	19:21	Off the coast of Fukushima Prefecture	5.5	3
	19:35	Off the coast of Fukushima Prefecture	5.0	2
	19:39	Off the coast of Miyagi Prefecture	4.9	1
	19:46	Off the coast of Ibaraki Prefecture	4.9	2
	20:00	Off the coast of Fukushima Prefecture	5.5	3
	20:07	Off the coast of Ibaraki Prefecture	4.7	2
	20:13	Off the coast of Ibaraki Prefecture	5.8	2
	20:17	Off the coast of Fukushima Prefecture	5.7	2
	20:20	Off the coast of Ibaraki Prefecture	5.7	2
	20:31	Southern Miyagi Prefecture	5.2	2
	20:36	Off the coast of Iwate Prefecture	6.7	3
	20:39	Off the coast of Miyagi Prefecture	5.5	2
	20:46	Off the coast of Ibaraki Prefecture	5.4	2
	20:56	Off the coast of Ibaraki Prefecture	5.4	1
	20:57	Off the coast of Iwate Prefecture	5.4	1

Date	Time	Information on hypocenter, magnitude, seismic intensity, tsunami, etc.		
		Hypocenter	Magnitude	Seismic intensity (Futabamachi, Fukushima)
March 11	21:13	Off the coast of Fukushima Prefecture	6.1	3
	21:15	Off the coast of Iwate Prefecture	5.9	2
	21:21	Off the coast of Fukushima Prefecture	4.9	3
	21:33	Off the coast of Sanriku	5.2	1
	21:49	Off the coast of Ibaraki Prefecture	5.2	2
	21:55	Off the coast of Miyagi Prefecture	5.1	3
	22:17	Off the coast of Ibaraki Prefecture	5.7	2
	22:33	Off the coast of Fukushima Prefecture	4.5	1
	22:34	Off the coast of Ibaraki Prefecture	5.6	1
	22:47	Off the coast of Fukushima Prefecture	4.7	1
	22:56	Off the coast of Fukushima Prefecture	5.3	2
	23:00	Off the coast of Ibaraki Prefecture	5.4	2
	23:10	Off the coast of Fukushima Prefecture	5.1	2
	23:44	Off the coast of Ibaraki Prefecture	4.9	2
	23:54	Off the coast of Ibaraki Prefecture	5.9	3
12-Mar	0:06	Off the coast of Fukushima Prefecture	5.3	2
	0:13	Off the coast of Ibaraki Prefecture	6.6	3
	0:15	Off the coast of Ibaraki Prefecture	5.4	2
	0:19	Off the coast of Ibaraki Prefecture	6.2	3
	0:24	Northern Gunma Prefecture	4.3	1
	0:26	Off the coast of Fukushima Prefecture	5.0	1
	0:32	Off the coast of Fukushima Prefecture	5.3	1
	0:42	Off the coast of Ibaraki Prefecture	5.5	1
	0:51	Off the coast of Fukushima Prefecture	5.2	1
	1:49	Off the coast of Ibaraki Prefecture	4.7	1
	1:57	Off the coast of Miyagi Prefecture	4.8	1
	2:30	Off the coast of Fukushima Prefecture	5.0	3
	2:56	Off the coast of Fukushima Prefecture	4.4	3
	3:11	Off the coast of Fukushima Prefecture	6.0	3
	3:44	Off the coast of Fukushima Prefecture	5.0	2
	3:59	Northern Nagano Prefecture	6.7	3
	4:02	Off the coast of Sanriku	6.3	2
	4:08	Off the coast of Ibaraki Prefecture	5.2	2
	4:09	Northern Nagano Prefecture	4.5	1
	4:16	Off the coast of Fukushima Prefecture	4.1	1
	4:24	Off the east coast of Chiba Prefecture	5.7	2
	4:31	Northern Nagano Prefecture	5.9	2
	4:45	Off the coast of Fukushima Prefecture	5.2	3
	4:46	Off the coast of Akita Prefecture	6.4	1

Date	Time	Information on hypocenter, magnitude, seismic intensity, tsunami, etc.		
		Hypocenter	Magnitude	Seismic intensity (Futabamachi, Fukushima)
12-Mar	5:11	Off the coast of Sanriku	6.4	2
	5:25	Off the coast of Fukushima Prefecture	4.9	2
	5:34	Off the coast of Fukushima Prefecture	5.0	2
	6:34	Off the coast of Fukushima Prefecture	4.8	3
	8:11	Hamadori, Fukushima Prefecture	4.6	2
	8:54	Off the coast of Fukushima Prefecture	5.0	2
	8:59	Off the coast of Ibaraki Prefecture	5.5	2
	9:25	Off the coast of Fukushima Prefecture	4.9	2
	10:04	Off the coast of Miyagi Prefecture	4.8	2
	10:12	Hamadori, Fukushima Prefecture	4.8	2
	10:13	Off the coast of Fukushima Prefecture	4.7	3
	10:35	Off the coast of Sanriku	5.8	1
	10:46	Off the coast of Fukushima Prefecture	5.2	2
	10:47	Off the coast of Fukushima Prefecture	6.8	3
	11:34	Off the coast of Fukushima Prefecture	5.2	2
	11:52	Off the coast of Fukushima Prefecture	5.0	2
	12:12	Off the coast of Ibaraki Prefecture	5.6	2
	13:06	Off the coast of Miyagi Prefecture	5.3	2
	14:14	Northern Ibaraki Prefecture	4.9	1
	14:45	Off the coast of Fukushima Prefecture	4.5	2
	15:18	Off the coast of Iwate Prefecture	5.5	2
	15:44	Off the coast of Ibaraki Prefecture	4.7	1
	16:36	Off the coast of Fukushima Prefecture	4.7	2
	19:53	Off the coast of Miyagi Prefecture	5.8	2
	20:20	"Major tsunami warnings" were changed to "tsunami warnings." (Fukushima Prefecture)		
	21:54	Off the coast of Sanriku	5.9	2
	22:15	Off the coast of Fukushima Prefecture	6.2	4
	22:24	Off the coast of Miyagi Prefecture	4.8	1
	23:14	Off the coast of Ibaraki Prefecture	5.2	1
	23:33	Off the coast of Ibaraki Prefecture	4.3	1
	23:43	Off the coast of Iwate Prefecture	5.9	2
13-Mar	3:09	Off the coast of Fukushima Prefecture	4.5	3
	5:41	Off the coast of Fukushima Prefecture	4.7	2
	6:58	Off the coast of Iwate Prefecture	5.4	1
	7:13	Off the coast of Fukushima Prefecture	6.0	3
	7:30	"Tsunami warnings" were changed to "tsunami advisories." (Fukushima Prefecture)		
	7:59	Off the coast of Fukushima Prefecture	4.4	2
	8:24	Off the coast of Miyagi Prefecture	6.2	4
	8:41	Off the coast of Fukushima Prefecture	5.2	1

Date	Time	Information on hypocenter, magnitude, seismic intensity, tsunami, etc.		
		Hypocenter	Magnitude	Seismic intensity (Futabamachi, Fukushima)
13-Mar	9:41	Off the coast of Ibaraki Prefecture	4.5	1
	10:26	Off the coast of Ibaraki Prefecture	6.6	2
	14:59	Off the coast of Fukushima Prefecture	4.7	3
	17:58	"Tsunami advisories" were cancelled. (Fukushima Prefecture)		
	20:37	Off the coast of Fukushima Prefecture	6.0	3
	21:44	Off the coast of Fukushima Prefecture	4.7	2
14-Mar	2:04	Off the coast of Fukushima Prefecture	4.4	1
	2:55	Off the east coast of Chiba Prefecture	5.7	2
	4:27	Off the coast of Fukushima Prefecture	4.2	1
	8:41	Off the coast of Ibaraki Prefecture	4.7	2
	10:02	Off the coast of Ibaraki Prefecture	6.2	3
	13:45	Off the coast of Fukushima Prefecture	4.7	2
	15:12	Off the coast of Miyagi Prefecture	6.5	3
	15:18	Off the coast of Fukushima Prefecture	5.2	3
	15:52	Off the coast of Fukushima Prefecture	5.2	3
	16:25	Off the coast of Ibaraki Prefecture	4.8	1
	18:07	Off the coast of Ibaraki Prefecture	4.8	2
March 15	3:35	Off the coast of Fukushima Prefecture	4.3	2
	3:41	Off the coast of Ibaraki Prefecture	5.6	2
	4:28	Off the coast of Miyagi Prefecture	5.0	1
	16:03	Northern Ibaraki Prefecture	4.9	2
	16:48	Off the coast of Fukushima Prefecture	4.3	1
	18:50	Off the coast of Fukushima Prefecture	6.3	2
	20:06	Off the coast of Fukushima Prefecture	5.2	2
	22:27	Off the coast of Fukushima Prefecture	6.2	4
	22:31	Eastern Shizuoka Prefecture	6.4	2
	22:37	Off the coast of Fukushima Prefecture	5.3	2
March 16	5:53	Hamadori, Fukushima Prefecture	4.5	1
	12:23	Off the coast of Fukushima Prefecture	4.6	2
	12:52	Off the east coast of Chiba Prefecture	6.1	3
	13:14	Off the coast of Fukushima Prefecture	5.6	4
	15:29	Off the coast of Iwate Prefecture	5.6	2
	18:15	Off the coast of Fukushima Prefecture	4.6	2
	20:45	Off the coast of Fukushima Prefecture	4.4	2
	22:39	Southern Ibaraki Prefecture	5.4	2
	22:54	Off the coast of Fukushima Prefecture	4.6	3
	23:46	Off the coast of Miyagi Prefecture	5.3	2
March 17	3:56	Hamadori, Fukushima Prefecture	4.4	1
	4:00	Off the coast of Fukushima Prefecture	4.5	1

Date	Time	Information on hypocenter, magnitude, seismic intensity, tsunami, etc.		
		Hypocenter	Magnitude	Seismic intensity (Futabamachi, Fukushima)
March 17	13:13	Off the coast of Iwate Prefecture	5.9	2
	17:25	Off the coast of Ibaraki Prefecture	5.4	2
	20:48	Off the coast of Fukushima Prefecture	4.4	2
	21:35	Off the coast of Fukushima Prefecture	5.1	2
	21:54	Off the coast of Ibaraki Prefecture	5.7	3
March 18	3:38	Off the coast of Fukushima Prefecture	4.7	3
	3:55	Off the coast of Fukushima Prefecture	5.7	2
	6:18	Off the coast of Fukushima Prefecture	4.5	2
	11:48	Off the coast of Fukushima Prefecture	5.1	2
	17:01	Off the east coast of Chiba Prefecture	5.4	2
March 19	4:53	Off the coast of Fukushima Prefecture	5.1	2
	8:32	Off the coast of Iwate Prefecture	5.7	2
	8:49	Off the coast of Fukushima Prefecture	5.3	2
	18:56	Northern Ibaraki Prefecture	6.1	4
20-Mar	5:48	Off the coast of Fukushima Prefecture	4.5	2
	10:30	Off the coast of Fukushima Prefecture	5.5	3
20-Mar	14:19	Hamadori, Fukushima Prefecture	4.6	2
	14:55	Off the coast of Fukushima Prefecture	5.4	3
	21:03	Off the coast of Iwate Prefecture	5.9	2
21-Mar	4:54	Off the coast of Fukushima Prefecture	4.6	3
	4:59	Off the coast of Fukushima Prefecture	4.2	3
	5:05	Off the coast of Fukushima Prefecture	4.5	2
	8:43	Off the coast of Fukushima Prefecture	4.6	1
	14:08	Off the coast of Ibaraki Prefecture	5.2	1
22-Mar	6:24	Off the coast of Ibaraki Prefecture	4.3	1
	16:18	Off the coast of Fukushima Prefecture	6.7	2
	17:33	Off the coast of Ibaraki Prefecture	4.7	1
	18:19	Off the coast of Fukushima Prefecture	6.4	4
	18:44	Off the coast of Sanriku	6.5	3
	21:04	Off the coast of Ibaraki Prefecture	5.9	3
	22:51	Off the coast of Ibaraki Prefecture	5.9	2
23-Mar	0:03	Off the coast of Ibaraki Prefecture	5.9	1
	7:12	Hamadori, Fukushima Prefecture	6.0	4
	7:34	Hamadori, Fukushima Prefecture	5.5	3
	7:36	Hamadori, Fukushima Prefecture	5.8	3
	7:53	Hamadori, Fukushima Prefecture	5.1	1
	18:55	Hamadori, Fukushima Prefecture	4.7	2
	19:43	Off the coast of Ibaraki Prefecture	5.1	2
24-Mar	8:56	Southern Ibaraki Prefecture	4.8	1


Date	Time	Information on hypocenter, magnitude, seismic intensity, tsunami, etc.		
		Hypocenter	Magnitude	Seismic intensity (Futabamachi, Fukushima)
24-Mar	17:20	Off the coast of Iwate Prefecture	6.2	3
25-Mar	2:08	Northern Ibaraki Prefecture	4.7	1
	3:16	Off the coast of Ibaraki Prefecture	4.3	1
	4:44	Off the coast of Miyagi Prefecture	4.8	1
26-Mar	19:18	Off the coast of Miyagi Prefecture	5.2	2
27-Mar	1:07	Off the coast of Ibaraki Prefecture	4.4	1
	20:08	Off the coast of Fukushima Prefecture	4.5	2
28-Mar	6:11	Off the coast of Ibaraki Prefecture	4.7	1
	7:23	Off the coast of Miyagi Prefecture	6.5	4
29-Mar	16:04	Off the coast of Fukushima Prefecture	4.3	3
	19:54	Off the coast of Fukushima Prefecture	6.6	3
30-Mar	22:00	Off the coast of Miyagi Prefecture	5.1	2
	22:19	Off the coast of Ibaraki Prefecture	5.0	2
31-Mar	16:15	Off the coast of Miyagi Prefecture	6.1	2

Explanatory note)

	Earthquake with observed intensity 6 at Futabamachi, Fukushima Prefecture
	Earthquake with observed intensity 5 at Futabamachi, Fukushima Prefecture
	Earthquake with observed intensity 4 at Futabamachi, Fukushima Prefecture
	Tsunami information and tsunami warnings/advisories

Based on the information on earthquakes, tsunamis and tsunami warnings/advisories

* The starting time of the first waves of the tsunami was unidentified from the tidal data due to changes in tidal level caused by quakes and other factors.



Photographed by Tokyo Electric Power Company
15:43, March 11, 2011

Ground deformation caused by quakes is not reflected in inundation height or run-up height.

Investigation results concerning the flooding of the Fukushima Dai-ichi NPS by the tsunami (level of inundation, water depth and flooded area)


Based on "The impact of Tohoku-Chihou Taiheiyo-Oki Earthquake to Nuclear Reactor Facilities at Fukushima Dai-ichi Nuclear Power Station" (September 2011) by Tokyo Electric Power Company

Radiation dose in R/B, T/B, etc., and the location of facilities housed therein


Unit 1

- This document describes the latest dose information provided by Tokyo Electric Power Company (TEPCO) while being based on the “Survey Map” which TEPCO created in order to organize past dose data for the purpose of radiation control.
- In addition, the document indicates the main facilities inside each building.
- The numbers in the figures indicate the radiation doses (mSv/h) measured at the respective spots. The colors circling the numbers correspond to the measurement dates listed in the margins of the figures.
- The radiation dose measurements were conducted for thirty-three days, from July 22 to October 1.

Unit for numbers in the document
-Dose: mSv/h





Fifth floor, R/B, Unit 1




Fourth floor, R/B, Unit 1

Based on data and documents by Tokyo Electric Power Company


The parts colored in pale-blue in the documents on Units 1 to 4 indicate the areas considered to have been under water based on the level of residual water inside buildings as of October 4.



Based on data and documents by Tokyo Electric Power Company




First floor, R/B, Unit 1




Basement mezzanine floor, R/B, Unit 1

Based on data and documents by Tokyo Electric Power Company




September 13, 2011




First basement floor, T/B Unit 1

Based on documents and data created by TEPCO




Fifth floor, R/B, Unit 2




Fourth floor, R/B, Unit 2

Based on data and documents by Tokyo Electric Power Company




Third floor, R/B, Unit 2




Second floor, R/B, Unit 2

Based on data and documents by Tokyo Electric Power Company




Common auxiliary facilities

Shared pool building



M/C 2SA building




*Refer to Attachments II-3 and II-4 for the location of common auxiliary facilities (shared pool building).

*Refer to Attachment II-4 for the location of the M/C 2SA building.


September 15, 2011

First floor, R/B, Unit 2




Basement mezzanine floor, R/B, Unit 2

Based on data and documents by Tokyo Electric Power Company





First basement floor, R/B, Unit 2




Based on data and documents by Tokyo Electric Power Company

- July 27, 2011
- August 17, 2011
- September 1, 2011
- September 3, 2011
- September 8, 2011
- September 21, 2011




First basement floor, T/B, Unit 2

Based on data and documents by Tokyo Electric Power Company




Fifth floor, R/B, Unit 3



Fourth floor, R/B, Unit 3


Based on data and documents by Tokyo Electric Power Company



Third floor, R/B, Unit 3


July 26, 2011

July 27, 2011




Second floor, R/B, Unit 3


Based on data and documents by Tokyo Electric Power Company




First floor, R/B, Unit 3



Basement mezzanine floor, R/B, Unit 3





First basement floor, R/B, Unit 3




Second floor, T/B, Unit 3

July 22, 2011

September 15, 2011



This basement mezzanine floor is located above the area in the green dashed line on the first basement floor, T/B, Unit 3.




Basement mezzanine floor, C/B

Basement mezzanine floor, T/B, Unit 3

Based on data and documents by Tokyo Electric Power Company




Fifth floor, R/B, Unit 4



Fourth floor, R/B, Unit 4


Based on data and documents by Tokyo Electric Power Company

July 28, 2011




Third floor, R/B, Unit 4

July 28, 2011




Second floor, R/B, Unit 4

Based on data and documents by Tokyo Electric Power Company




First floor, R/B, Unit 4




Basement mezzanine floor, R/B, Unit 4

Based on data and documents by Tokyo Electric Power Company




First basement floor, R/B, Unit 4


August 27, 2011



Based on data and documents by Tokyo Electric Power Company




First floor, T/B, Unit 4



First basement floor, T/B, Unit 4


September 26, 2011



The parts colored in pale-blue in the document indicate the areas where workers of Tokyo Electric Power Company confirmed residual water puddles from August 18 to 30.

Fifth floor, R/B, Unit 5

July 22, 2011




Fourth floor, R/B, Unit 5

Based on data and documents by Tokyo Electric Power Company


July 22, 2011

September 29, 2011



Third floor, R/B, Unit 5

July 22, 2011




Second floor, R/B, Unit 5


Based on data and documents by Tokyo Electric Power Company

July 22, 2011

September 27, 2011




First floor, R/B, Unit 5




Basement mezzanine floor, R/B, Unit 5

Based on data and documents by Tokyo Electric Power Company



First basement floor, R/B, Unit 5


July 22, 2011



Second floor, T/B, Unit 5

Based on data and documents by Tokyo Electric Power Company

July 22, 2011




First floor, T/B, Unit 5

July 22, 2011

September 21, 2011


The basement mezzanine floor, T/B, Unit 5 is located above this purple area.



First basement, C/B

First basement floor, T/B, Unit5

Based on data and documents by Tokyo Electric Power Company




Basement mezzanine floor, T/B, Unit 5

- This basement mezzanine floor is located above the purple area on the first basement floor, T/B, Unit 5.
- The Unit 6 DC power source system is also installed on this floor.

Based on data and documents by Tokyo Electric Power Company

July 22, 2011


September 27, 2011



Sixth floor, R/B, Unit 6


July 22, 2011

September 30, 2011




Fifth floor, R/B, Unit 6

July 22, 2011



Fourth floor, R/B, Unit 6


July 22, 2011



Third floor, R/B, Unit 6

Based on data and documents by Tokyo Electric Power Company


July 22, 2011




Second floor, R/B, Unit 6

July 22, 2011

Diesel generator building





* Refer to Attachment II-4 for the location of the diesel generator building.




First floor, R/B, Unit 6

Based on data and documents by Tokyo Electric Power Company




Based on data and documents by Tokyo Electric Power Company

July 22, 2011




Second floor, T/B, Unit 6

July 22, 2011



First floor, T/B, Unit 6

July 22, 2011




First basement floor, T/B, Unit 6

Based on data and documents by Tokyo Electric Power Company

Structures and components inside the reactor pressure vessel

Attachment II-13


Unit 1



Source: Tokyo Electric Power Company, "Fukushima Dai-ichi NPS: Application for reactor establishment permit," April 2002

Structures and components inside the reactor pressure vessel


Units 2-5



Source: Tokyo Electric Power Company, "Fukushima Dai-ichi NPS: Application for permit for changes to reactor establishment" (as of June 2003)


Structures and components inside the reactor pressure vessel


Unit 6



Source: Tokyo Electric Power Company, "Fukushima Dai-ichi NPS: Application for permit for changes to reactor establishment" (as of December 2010)

Principle of measurement by reactor water level and reactor pressure instrumentation systems






Sectional lines are referred to from the preparation of sectional views of the reactor building and other facilities at Units 5 and 6 of the Fukushima Dai-ichi NPS

Based on data and documents by Tokyo Electric Power Company


Sectional view of the reactor building and other facilities at Unit 1 of the Fukushima Dai-ichi NPS



Source: Tokyo Electric Power Company, "Fukushima Dai-ichi NPS: Application for reactor alternation license," April 2002

Sectional view of the reactor building and other facilities at Unit 2 of the Fukushima Dai-ichi NPS

A	Reactor building	1	Condenser
B	Turbine building	2	Turbine generator
C	Radioactive waste building	3	Crane
		4	Reactor
		5	Drywell
		6	Suppression chamber
		7	Fuel storage pool
		8	Storage pool for the steam separator and other equipment




Section A-A


Section B-B

Source: Tokyo Electric Power Company, "Fukushima Dai-ichi NPS: Application for reactor alternation license," April 2002

Sectional view of the reactor building and other facilities at Unit 3 of the Fukushima Dai-ichi NPS





Section A-A



Section B-B



Based on "Fukushima Dai-ichi NPS: Application for reactor alternation license" (June 2003) by Tokyo Electric Power Company

Sectional view of the reactor building and other facilities at Unit 4 of the Fukushima Dai-ichi NPS





Based on "Fukushima Dai-ichi NPS: Application for reactor alternation license" (June 2003) by Tokyo Electric Power Company

Sectional view of the reactor building and other facilities at Unit 5 of the Fukushima Dai-ichi NPS



Based on "Fukushima Dai-ichi NPS: Application for reactor alternation license" (June 2003) by Tokyo Electric Power Company

Sectional view of the reactor building and other facilities at Unit 6 of the Fukushima Dai-ichi NPS



Source: Tokyo Electric Power Company, "Fukushima Dai-ichi NPS: Application for reactor alternation license," December 2010

福島第一原子力発電所における 4 号機の原子炉建屋等の断面図 : Sectional view of the reactor building and other facilities at Unit 4 of the Fukushima Dai-ichi NPS

上図 左 ⇒ 右

- ①使用済樹脂貯蔵タンク : Spent resin storage tank
- ②廃スラッジ貯蔵タンク : Waste sludge storage tank
- ③R/B クレーン (100/5 TON) : R/B crane (100/5 ton)
- ④γ シールドプラグ : Gamma shield plug
- ⑤M-G セット : M/G set
- ⑥燃料プール冷却系熱交換器 : Heat exchanger of the fuel pool cooling system
- ⑦OP 36,800 (内側) : OP 36,800 (interior side)
- ⑧SLC タンク : SLC tank
- ⑨圧力容器 : Pressure vessel
- ⑩CUW 再循環ポンプ : CUW recirculation pump
- ⑪再循環ポンプ : recirculation pump
- ⑫サプレッションチェンバ : Suppression chamber
- ⑬空調機器室 : Air-conditioning equipment room
- ⑭給水管 : Feedwater line
- ⑮主蒸気管 : Main steam line
- ⑯空調機器室 : Air-conditioning equipment room
- ⑰給水加熱器 : Feedwater heater
- ⑱給水加熱器 : Feedwater heater
- ⑲原子炉給水ポンプ : Reactor feed water pump
- ⑳175 t クレーン : 175-ton crane
- ㉑CIV バルブ : CIV valve
- ㉒給水加熱器 : Feedwater heater
- ㉓復水器 : Condenser
- ㉔循環水管 : Circulating water line

下図 左 ⇒ 右

- ㉕樹脂貯槽 : Resin reservoir
- ㉖密封油制御装置 : Seal oil control system
- ㉗空気貯槽 : Air reservoir
- ㉘配管トレンチ : Pipe trench
- ㉙発電機 : Generator

- ⑩ 固定予冷却装置 : Fixed pre-cooling unit
- ⑪ ホールドアップパイプ : Holdup pipes
- ⑫ タービン : Turbine
- ⑬ 給水加熱器 : Feedwater heater
- ⑭ 復水器 : Condenser
- ⑮ 湿分分離器 : Moisture separator
- ⑯ 湿分分離器ドレンタンク : Moisture separator drain tank
- ⑰ 主蒸気止メ弁 : Main steam stop valve
- ⑱ タービンバイパス弁 : Turbine bypass valve
- ⑲ 配管トレンチ : Pipe trench
- ⑳ タービンオイルタンク : Turbine oil tank
- ㉑ 6.9 kV スイッチギア : 6.9 kV switch gear
- ㉒ トラス上面 : Upper surface of the truss
- ㉓ レール上面 : Upper surface of the rail

福島第一原子力発電所における 5 号機の原子炉建屋等の断面図 : Sectional view of the reactor building and other facilities at Unit 5 of the Fukushima Dai-ichi NPS

上図 左 ⇒ 右

- ① R/B クレーン : R/B crane
- ② 原子炉建屋 : Reactor building
- ③ モーター発電機室 : Motor-driven generator room
- ④ ドライウェル : Drywell
- ⑤ サプレッションチェンバ : Suppression chamber
- ⑥ 空調機器室 : Air-conditioning equipment room
- ⑦ 空調機器室 : Air-conditioning equipment room
- ⑧ T/B クレーン : T/B crane
- ⑨ タービン建屋 : Turbine building
- ⑩ タービン : Turbine
- ⑪ 復水器 : Condenser

下図 左 ⇒ 右

- ⑫ 発電機冷却装置 : Generator cooling unit

- ⑬タービン：Turbine
- ⑭復水器：Condenser
- ⑮湿分分離器：Moisture separator
- ⑯バルブ室：Valve room
- ⑰タービン油タンク：Turbine oil tank
- ⑱タービン貯油タンク：Turbine oil storage tank
- ⑲バッテリー室：Battery room
- ⑳スイッチギア室：Switch gear room

福島第一原子力発電所における 6 号機の原子炉建屋等の断面図：Sectional view of the reactor building and other facilities at Unit 6 of the Fukushima Dai-ichi NPS

上図 左 ⇒ 右

- ①原子炉建屋：Reactor building
- ②R／B クレーン：R/B crane
- ③気水分離器等貯蔵プール：Storage pool for the steam separator and other devices
- ④原子炉浄化系熱交換器：Heat exchanger of the reactor cleanup system
- ⑤使用済燃料プール：Cartridge cooling pond
- ⑥再循環ポンプ：Recirculation pump
- ⑦原子炉圧力容器：Reactor pressure vessel
- ⑧燃料プール熱交換器：Fuel pool heat exchanger
- ⑨廃棄物貯蔵建屋：Waste storage building
- ⑩廃スラッジ貯蔵タンク：Waste sludge storage tank
- ⑪活性炭ホールドアップ装置室：Charcoal equipment room
- ⑫H P C S ポンプ：HPCS pump
- ⑬サプレッションプール：Suppression pool
- ⑭パイプトンネル：Pipe tunnel
- ⑮R H R 熱交換器：RHR heat exchanger
- ⑯R H R ポンプ：RHR pump
- ⑰空調機械室：Air-conditioning machine room
- ⑱給水加熱器：Feedwater heater
- ⑲給水加熱器：Feedwater heater
- ⑳タービン建屋：Turbine building
- ㉑T／B クレーン：T/B crane

- ㉒タービン駆動給水ポンプ：Turbine-driven feedwater pump
- ㉓タービン発電機：Turbine-generator
- ㉔給水加熱器：Feedwater heater
- ㉕復水器：Condenser
- ㉖補機冷却熱交換器：Component cooling heat exchanger

下図 左 ⇒ 右

- ㉗ディーゼル発電機建屋：Diesel generator building
- ㉘非常用ディーゼル発電機室：Emergency diesel generator room
- ㉙冷却材再循環ポンプ：Recirculation internal pump
- ㉚M／Gセット：M/G set
- ㉛復水脱塩塔：Condensate demineralization tower
- ㉜樹脂ストレーナ：Resin strainer
- ㉝発電機：Generator
- ㉞機械式真空ポンプ：Mechanical vacuum pump
- ㉟空気抽出器：Air ejector
- ㊱給水加熱器：Feedwater heater
- ㊲低圧タービン：Low-pressure turbine
- ㊳復水器：Condenser
- ㊴遮蔽装置：Shielding device
- ㊵高圧タービン：High-pressure turbine
- ㊶湿分分離器：Moisture separator
- ㊷給水ポンプ潤滑油タンク：Lubricant oil tank of the feedwater pump
- ㊸給水加熱器ドレンポンプ：Heater drain pump

Photographs showing damage to the Unit 1 reactor building



March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company

Photographs showing damage to the Unit 1 reactor building



March 12, 2011
Photographed by Tokyo Electric Power Company



May 22, 2011
Photographed by Tokyo Electric Power Company




April 14, 2011
Photographed by Tokyo Electric Power Company




April 15, 2011
Photographed by Tokyo Electric Power Company


Photographs showing damage to the Unit 3 reactor building




March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company




March 24, 2011
Photographed by Tokyo Electric Power Company


Photographs showing damage to the Unit 4 reactor building



March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company

Photographs showing damage to the Unit 4 reactor building



March 24, 2011
Photographed by Tokyo Electric Power Company



March 24, 2011
Photographed by Tokyo Electric Power Company




March 24, 2011
Photographed by Tokyo Electric Power Company




March 24, 2011
Photographed by Tokyo Electric Power Company

Isolation Condenser (IC)




Created by Tokyo Electric Power Company



Reactor core isolation cooling (RCIC) system


Based on "Fukushima Dai-ichi NPS: Application for permit for changes to reactor establishment"
(June 2003) by Tokyo Electric Power Company



High pressure coolant injection (HPCI) system

Based on "Fukushima Dai-ichi NPS: Application for permit for changes to reactor establishment"
(June 2003) by Tokyo Electric Power Company

Photograph showing an overview of the seaside area and outdoor seawater facilities at the Fukushima Dai-ichi NPS



RHRS: Residual heat removal sea water system
 CCSW: Containment cooling sea water system
 DGSW: Diesel generator sea water system

The aerial pictures are created from photographs on GeoEye.
 The six pictures in the bottom row are created from photographs taken by Tokyo Electric Power Company on March 29, 2011.

Damage to the emergency diesel generators (DGs), metal clad switchgear (M/C) and power centers (P/Cs)

Table 1. Damage to the emergency diesel generators (DGs) after the arrival of the tsunami

	Equipment	Installation location	Remarks	Equipment	Installation location	Remarks	Equipment	Installation location	Remarks	Equipment	Installation location	Remarks	Equipment	Installation location	Remarks	Equipment	Installation location	Remarks
DG	Unit 1			Unit 2			Unit 3			Unit 4			Unit 5			Unit 6		
	1A	1st basement floor, T/B	-	2A	1st basement floor, T/B	-	3A	1st basement floor, T/B	-	4A	1st basement floor, T/B	-	5A	1st basement floor, T/B	Exciters exposed to water	6A	1st basement floor, R/B	Seawater pumps exposed to water
	1B	1st basement floor, T/B	-	2B	1st floor, shared pool	M/C (2E), submerged	3B	1st basement floor, T/B	-	4B	1st floor, shared pool	M/C (4E), exposure to water	5B	1st basement floor, T/B	Exciters exposed to water	6B	1st floor, DG bldg.	-
	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	for HPCS	1st basement floor, R/B	Seawater pumps exposed to water

Table 2. Damage to the metal clad switchgear (M/C) after the arrival of the tsunami

		Equipment	Installation location	Equipment	Installation location	Equipment	Installation location	Equipment	Installation location	Equipment	Installation location	Equipment	Installation location
		Unit 1		Unit 2		Unit 3		Unit 4		Unit 5		Unit 6	
Emergency M/C		1C	1st floor, T/B	2C	1st basement floor, T/B	3C	1st basement floor, T/B	4C	1st basement floor, T/B	5C	1st basement floor, T/B	6C	2nd basement floor, R/B
		1D	1st floor, T/B	2D	1st basement floor, T/B	3D	1st basement floor, T/B	4D	1st basement floor, T/B	5D	1st basement floor, T/B	6D	1st basement floor, R/B
		-	-	2E	1st basement floor, shared pool	-	-	4E	1st basement floor, shared pool	-	-	for HPCS	1st floor, R/B
Regular M/C	Regular	1A	1st floor, T/B	2A	1st basement floor, T/B	3A	1st basement floor, T/B	4A	1st basement floor, T/B	5A	1st basement floor, C/B	6A-1	1st basement floor, T/B
		1B	1st floor, T/B	2B	1st basement floor, T/B	3B	1st basement floor, T/B	4B	1st basement floor, T/B	5B	1st basement floor, C/B	6A-2	1st basement floor, T/B
		-	-	-	-	-	-	-	-	-	-	6B-1	1st basement floor, T/B
		-	-	-	-	-	-	-	-	-	-	6B-2	1st basement floor, T/B
	Common	1S	1st floor, T/B	2SA	1st floor, 2SA bldg.	3SA	1st basement floor, C/B	-	-	5SA-1	1st basement floor, C/B	-	-
		-	-	2SB	1st basement floor, T/B	3SB	1st basement floor, C/B	-	-	5SA-2	1st basement floor, C/B	-	-
		-	-	-	-	-	-	-	-	5SB-1	1st basement floor, C/B	-	-
		-	-	-	-	-	-	-	-	5SB-2	1st basement floor, C/B	-	-

Table 3. Damage to the power centers (P/Cs) after the arrival of the tsunami

		Equipment	Installation location	Equipment	Installation location	Equipment	Installation location	Equipment	Installation location	Equipment	Installation location	Equipment	Installation location
		Unit 1		Unit 2		Unit 3		Unit 4		Unit 5		Unit 6	
Emergency P/C		1C	1st basement floor, C/B	2C	1st floor, T/B	3C	1st basement floor, T/B	4C	1st floor, T/B	5C	1st basement floor, T/B	6C	2nd basement floor, R/B
		1D	1st basement floor, C/B	2D	1st floor, T/B	3D	1st basement floor, T/B	4D	1st floor, T/B	5D	1st basement floor, T/B	6D	1st basement floor, R/B
		-	-	2E	1st basement floor, shared pool	-	-	4E	1st basement floor, shared pool	-	-	6E	1st basement floor, DG bldg.
Regular P/C	Regular	1A	1st floor, T/B	2A	1st floor, T/B	3A	1st basement floor, T/B	4A	1st floor, T/B	5A	1st basement floor, C/B	6A-1	1st basement floor, T/B
		1B	1st floor, T/B	2A-1	1st basement floor, T/B	3B	1st basement floor, T/B	4B	1st floor, T/B	5A-1	2nd floor, T/B	6A-2	1st basement floor, T/B
		-	-	2B	1st floor, T/B	-	-	-	-	5B	1st basement floor, C/B	6B-1	1st basement floor, T/B
		-	-	-	-	-	-	-	-	5B-1	2nd floor, T/B	6B-2	1st basement floor, T/B
	Common	1S	1st floor, T/B	2SB	1st basement floor, T/B	3SA	1st basement floor, C/B	-	-	5SA	1st basement floor, C/B	-	-
		-	-	-	-	3SB	1st basement floor, C/B	-	-	5SA-1	1st basement floor, T/B	-	-
		-	-	-	-	-	-	-	-	5SB	1st basement floor, C/B	-	-

Explanatory note: The colors inside cells indicate the following:

Pink: Equipment itself was exposed to water.

Blue: Equipment was not exposed to water.

Green: Equipment itself was not exposed to water, but lost function due to water exposure of related equipment.

Gray: Under construction.

* Refer to Attachment II-3 for the location of each building, and to Attachment II-12 for the installation locations of the respective facilities inside the buildings.

* Refer to “Photographs showing damage to M/Cs and P/Cs” for the conditions of M/Cs and P/Cs of Unit 1, which were exposed to water.

Based on “The impact of Tohoku-Chihou Taiheiyo-Oki Earthquake to Nuclear Reactor Facilities at the Fukushima Dai-ichi Nuclear Power Station” (September 2011) by Tokyo Electric Power Company

Photographs showing damage to M/Cs and P/Cs



August 25, 2011 Photographed by Tokyo Electric Power Company

Picture (i): M/C on the north of the first floor, Unit 1 turbine building.
(Traces of the tsunami remain at shoulder height.)



August 25, 2011 Photographed by Tokyo Electric Power Company


Picture (ii): M/C on the north of the first floor, Unit 1 turbine building.
(The device in the back is a breaker drawn out of the box.)



August 25, 2011 Photographed by Tokyo Electric Power Company

Picture (iii): P/C-1S on the first floor, Unit 1 turbine building.

Illustration of damage to electrical installations inside and outside the premises of the Fukushima Dai-ichi NPS



* The figure does not include L1 and L2 of the Futaba Transmission Line, the power transmission lines from Units 5 and 6, and the ultrahigh voltage switching station for Units 5 and 6 because they only serve for power transmission.

Based on "Regarding Collection of Reports Pursuant to the Provisions of Article 106, Paragraph 3 of the Electricity Business Act" (May 16, 2011) by Tokyo Electric Power Company

Explanatory note

⊗	Isolator	■	Exposed to water due to the tsunami
●	Breaker	■	Under inspection/construction
⊕	Startup transformer	≡	Transformer
⊙	Power generator	✕	Cutting point in power supply

Photographs showing damage to facilities required for the supply of external power



March 23, 2011 Photographed by Tokyo Electric Power Company
Picture (i): Breaker (O-81) having fallen inside the switching station for Units 1 and 2.




March 23, 2011 Photographed by Tokyo Electric Power Company
Picture (ii): Breaker (O-82) having fallen inside the switching station for Units 1 and 2.



March 23, 2011 Photographed by Tokyo Electric Power Company
Picture (iii): Disconnection switch having fallen inside the switching station for Units 1 and 2.


- The respective numbers for the breakers (O-81 and O-82) correspond to those in Attachment II-22.

Photographs showing damage to facilities required for the supply of external power



Picture (iv): Arc scratches confirmed on L3 of the Okuma Transmission Line (Pylon No.7 of L3 and L4 of the Okuma Transmission Line).

(May 19, 2011 Photographed by Tokyo Electric Power Company)



Picture (v): Arc scratches confirmed on L4 of the Okuma Transmission Line (Pylon No. 11 of L3 and L4 of the Okuma Transmission Line.)

(May 19, 2011 Photographed by Tokyo Electric Power Company)

*The locations of Pylons No. 7 and 11 are as indicated in L3 and L4 of the Okuma Transmission Line in Attachment II-22.

Photographs showing damage to facilities required for the supply of external power



March 12, 2011 Photographed by Tokyo Electric Power Company


Picture (vi): Disconnected ground wire inside the Shin Fukushima Substation (Okuma Transmission Line, L3).



March 11, 2011 Photographed by Tokyo Electric Power Company

Picture (vii): Tilted steel structure for lead-in, Okuma Transmission Line, L3 and L4.

Photographs showing damage to facilities required for the supply of external power



Landside on the slope (Viewpoint (i))




Collapse of the pylon (Viewpoint (ii))



- Top picture showing the landslide: Photographed by ©Geo Eye on March 19, 2011.


- Pictures from Viewpoints (i) and (ii): Photographed by Tokyo Electric Power Company on March 18, 2011.

Picture (viii): Collapsed Pylon No. 27 of the Yorumori Transmission Line, L1 and L2.



Fire protection system piping layout at the Fukushima Dai-ichi NPS

Based on data and documents by Tokyo Electric Power Company.



Based on data and documents by Tokyo Electric Power Company

Fire protection system piping layout at the Fukushima Dai-ichi NPS (Units 5 and 6)

Location of the T/B water delivery ports at Units 1 to 4 of the Fukushima Dai-ichi NPS

* Construction completed in June 2010.

* Construction completed in June 2010.
Used for reactor coolant injection.

* Construction completed in June 2010.
Used for reactor coolant injection.

* Construction completed in June 2010.



Photographed by Tokyo Electric Power Company on August 1, 2011.



Photographed by Tokyo Electric Power Company on July 29, 2011.



Photographed by Tokyo Electric Power Company on September 26, 2011.

Photographed by Tokyo Electric Power Company on September 26, 2011.




Photograph taken from the depth of the photograph below facing toward the wall.



Photographed by Tokyo Electric Power Company on July 29, 2011.



Photographed by Tokyo Electric Power Company on August 1, 2011.



Attachment II-25

Explanatory note

- Installed on the side of the building. Construction completed in June 2010.
- Installed on the fire protection system piping. Construction completed in June 2010.
- Installed on the fire protection system piping. (Renovated in June 2010.)

Based on data and documents by Tokyo Electric Power Company

福島第一原子力発電所 1号機から 4号機 T／B送水口設置個所：Location of the T/B water delivery ports at Units 1 to 4 of the Fukushima Dai-ichi NPS

図上部 左⇒右

- ①機械室：Machine room
- ②放水口：Discharge structure
- ③ 4号機放水口：Discharge structure of Unit 4

図中央部 左⇒右

- ④事務本館別館：Annex of the main office building
- ⑤総合情報棟：General information building
- ⑥ 1号機復水貯蔵タンク：Unit 1 condensate storage tank
- ⑦逆洗弁ピット：Reversing valve pit
- ⑧ 2号機復水貯蔵タンク：Unit 2 condensate storage tank
- ⑨逆洗弁ピット：Reversing valve pit
- ⑩ 3号機復水貯蔵タンク：Unit 3 condensate storage tank
- ⑪立杭（A）：Shaft (A)
- ⑫逆洗弁ピット：Reversing valve pit
- ⑬立杭（D）：Shaft (D)
- ⑭北側立杭：North shaft
- ⑮逆洗弁ピット：Reversing valve pit
- ⑯南側立杭：South shaft
- ⑰ 1号機タービン建屋：Unit 1 turbine building
- ⑱ 1号機原子炉建屋：Unit 1 reactor building
- ⑲ 1， 2号機サービス建屋：Units 1 and 2 service building
- ⑳ 1， 2号機サービスエリア：Units 1 and 2 service area
- ㉑ 1号機コントロール建屋：Unit 1 control building
- ㉒ 2号機コントロール建屋：Unit 2 control building
- ㉓ 1号機廃棄物処理建屋：Unit 1 waste treatment building
- ㉔ 2号機廃棄物処理建屋：Unit 2 waste treatment building
- ㉕ 2号機タービン建屋：Unit 2 turbine building
- ㉖ 2号機原子炉建屋：Unit 2 reactor building
- ㉗起動変圧器：Startup transformer
- ㉘主変圧器：Main transformer
- ㉙地震観測小屋：Seismic observatory

- ⑩ チッ素供給装置 : Nitrogen-supplying device
- ⑪ 1, 2号機排気筒 : Stack for Units 1 and 2
- ⑫ 1, 2号機排気筒モニタ収納小屋 : Monitoring equipment chamber for Units 1 and 2 stack
- ⑬ 所内変圧器 : Auxiliary transformers
- ⑭ メタクラ2SA 建屋 : Metal clad switch gear 2SA building
- ⑮ 主変圧器 : Main transformer
- ⑯ 起動変圧器 : Startup transformer
- ⑰ 1～4号機共用所内ボイラ建屋 : Common auxiliary boiler building for Units 1-4
- ⑱ 3号機タービン建屋 : Unit 3 turbine building
- ⑲ 計算機室冷凍機 : Computer room cooler
- ⑳ 3号機廃棄物処理建屋 : Unit 3 waste treatment building
- ㉑ 3号機原子炉建屋 : Unit 3 reactor building
- ㉒ 所内変圧器 : Auxiliary transformers
- ㉓ 起動変圧器 : Startup transformer
- ㉔ 励磁電源変圧器 : Energizing power transformer
- ㉕ 主変圧器 : Main transformer
- ㉖ 3号機主発電機励磁装置盤建屋 : Building for the energizing device of Unit 3 main generator
- ㉗ 3, 4号機排気筒 : Stack for Units 3 and 4
- ㉘ 3, 4号機排気筒モニタ収納小屋 : Monitoring equipment chamber for Units 3 and 4 stack
- ㉙ 3, 4号機サービス建屋 : Units 3 and 4 service building
- ㉚ 3, 4号機サービスエリア : Units 3 and 4 service area
- ㉛ 3号機コントロール建屋 : Unit 3 control building
- ㉜ 4号機コントロール建屋 : Unit 4 control building
- ㉝ 4号機廃棄物処理建屋 : Unit 4 waste treatment building
- ㉞ 4号機タービン建屋 : Unit 4 turbine building
- ㉟ 4号機原子炉建屋 : Unit 4 reactor building
- ㊱ 所内変圧器 : Auxiliary transformer
- ㊲ 主変圧器 : Main transformer
- ㊳ 励磁電源変圧器 : Energizing power transformer
- ㊴ タービン建屋換気系排気筒 : Stack for the turbine building ventilation system
- ㊵ 排風気建屋 : Air-exhaust ventilation building
- ㊶ 放射性廃棄物集中処理施設(プロセス補助建屋) : Centralized radioactive waste treatment facilities (auxiliary processing building)
- ㊷ 重油タンク : Heavy oil tank
- ㊸ 軽油タンク : Light oil tank

- ㊦可燃性雑固体廃棄物焼却施設および工作機械室（焼工建屋）：Miscellaneous flammable solid waste combustor and engineering machine room (combustion building)
- ㊧放射性廃棄物集中処理施設（プロセス主建屋）：Centralized radioactive waste treatment facilities (main processing building)
- ㊨高放射性固体廃棄物処理建屋（サイトバンカー）：High activity solid waste treatment building (side banker)

図下部 左⇒右

- ㊩飲料水タンク：Drinking water tank
- ㊪1，2号機超高压開閉所：Ultrahigh voltage switching station for Units 1 and 2
- ㊫1～4号機共用所内ボイラ直流電源室：DC power supply room for the common station-service boiler for Units 1-4
- ㊬水素トレーラー：Hydrogen trailer
- ㊭液体酸素タンク：Liquid oxygen tank
- ㊮1，2号機活性炭ホールドアップ装置建屋：Units 1 and 2 charcoal building
- ㊯3号機活性炭ホールドアップ装置建屋：Unit 3 charcoal building
- ㊰3，4号機超高压開閉所：Ultrahigh voltage switching station for Units 3 and 4
- ㊱汚損検出器：Contamination detector
- ㊲軽油タンク：Light oil tanks
- ㊳軽油移送ポンプ：Light oil transfer pump
- ㊴運用補助共用施設（共用プール）：Common auxiliary facilities (shared pool)
- ㊵高温焼却建屋：High temperature incineration building
- ㊶重油タンク：Heavy oil tank
- ㊷共用サプレッションプールサージタンク建屋：Common suppression pool surge tank building

Location of the T/B water delivery ports at Units 5 and 6 of the Fukushima Dai-ichi NPS

* Construction completed in June 2010.




Photographed by Tokyo Electric Power Company on September 26, 2011.

* Construction completed in June 2010.



Photographed by Tokyo Electric Power Company on September 26, 2011.



- Explanatory note
- Installed on the side of the building. Construction completed in June 2010.
 - Installed on the fire protection system piping. (Renovated in June 2010.)

福島第一原子力発電所 5号機及び6号機 T/B送水口設置箇所 : Location of the T/B water delivery ports at Units 5 and 6 of the Fukushima Dai-ichi NPS

Location of the T/B water delivery ports at Units 1 to 4 of the Fukushima Dai-ichi NPS

図上部 左⇒右)

- ①取水口 : Water intake
- ②循環水ポンプ : Circulating water pump
- ③ 5, 6号機取水設備電源室 : Power room for Units 5 and 6 intake facilities
- ④取水口 : Water intake
- ⑤循環水ポンプ : Circulating water pump

図中央部 左⇒右

- ⑥ N o. 6 軽油タンク : Light oil tank No. 6
- ⑦ 6号機ディーゼル発電機建屋 : Unit 6 diesel generator building
- ⑧ 6号機MGセット建屋 : Unit 6 MG set building
- ⑨ 6号機タービン建屋 : Unit 6 turbine building
- ⑩ 5, 6号機サービス建屋 : Units 5 and 6 service building
- ⑪ N o. 3 軽油タンク : Light oil tank No. 3
- ⑫ 復水貯蔵タンク : Condensate storage tank
- ⑬ サービスエリア : Service area
- ⑭ 5号機タービン建屋 : Unit 5 turbine building
- ⑮ 5, 6号機コントロール建屋 : Units 5 and 6 control building
- ⑯ 6号機所内変圧器 : Unit 6 auxiliary transformers
- ⑰ 6号機主変圧器 : Unit 6 main transformer
- ⑱ 6号機復水貯蔵タンク : Unit 6 condensate storage tank
- ⑲ 電気品室 : Electrical item room
- ⑳ 非常用ディーゼル発電機室 : Emergency diesel generator room
- ㉑ 6号機原子炉建屋 : Unit 6 reactor building
- ㉒ 長期地震観測建屋 : Long-term seismic observation building
- ㉓ 5 / 6号機廃棄物地下貯蔵設備建屋 : Units 5 and 6 filter sludge tank room
- ㉔ 5号機起動変圧器 : Unit 5 startup transformers
- ㉕ 6号機雑固体処理建屋 : Unit 6 miscellaneous solid treatment building
- ㉖ 連絡通路 : Passageway
- ㉗ 廃棄物処理エリア : Waste treatment area
- ㉘ 主排気ダクト : Main exhaust air duct

- ㊸排気筒：Stack
- ㊹5，6号機排気筒モニタ収納小屋：Monitoring equipment chamber for the stack of Units 5 and 6
- ㊺5号機廃棄物処理建屋：Unit 5 waste treatment building
- ㊻5号所内ボイラー建屋：Unit 5 auxiliary boiler building
- ㊼5号機原子炉建屋：Unit 5 reactor building
- ㊽窒素供給装置：Nitrogen-supplying device
- ㊾主変圧器：Main transformer
- ㊿励磁変圧器：Energizing transformer
- ㋀所内変圧器：Auxiliary transformers
- ㋁水素供給設備制御盤室：Hydrogen-supplying facility control board room
- ㋂水素トレーラー：Hydrogen trailer
- ㋃純水タンク：Demineralized water tank
- ㋄N o . 4 資材倉庫：Material storage No.4

図下部 左⇒右

- ㋅6号機超高压開閉所：Ultrahigh voltage switching station for Unit 6
- ㋆5号機超高压開閉所：Ultrahigh voltage switching station for Unit 5
- ㋇66KV開閉所：66 kV switchyard

Photographs showing the installation
of outdoor fire protection system facilities
at the Fukushima Dai-ichi NPS



(i) Hydrant (FO-20)
August 24, 2011 Photographed by Tokyo Electric Power Company



(ii) Hydrant (FS-2)
August 24, 2011 Photographed by Tokyo Electric Power Company



(iii) Hydrant (FS-4)
August 24, 2011 Photographed by Tokyo Electric Power Company



(iv) Intake of the domestic water system
August 24, 2011 Photographed by Tokyo Electric Power Company



(v) Hydrant (FX-07)
August 24, 2011 Photographed by Tokyo Electric Power Company



(vi) Hydrant (F3-8)
August 24, 2011 Photographed by Tokyo Electric Power Company

* Of the entire outdoor fire extinguishing system, the pictures above show only examples of damage to facilities installed above ground.
(The condition of underground piping is yet to be confirmed.)

Photographs showing the installation of outdoor fire protection system facilities at the Fukushima Dai-ichi NPS




August 24, 2011 Photographed by Tokyo Electric Power Company



August 24, 2011 Photographed by Tokyo Electric Power Company



August 24, 2011 Photographed by Tokyo Electric Power Company



August 24, 2011 Photographed by Tokyo Electric Power Company



August 25, 2011 Photographed by Tokyo Electric Power Company



August 25, 2011 Photographed by Tokyo Electric Power Company

* Of the entire outdoor fire extinguishing system, the pictures above show only examples of damage to facilities installed above ground.
(The condition of underground piping is yet to be confirmed.)

Photographs showing the installation of outdoor fire protection system facilities at the Fukushima Dai-ichi NPS




(xiii) Hydrant (FX-01)
August 25, 2011 Photographed by Tokyo Electric Power Company



(xiv) Hydrant and other equipment (FX-04, FP-407)
August 25, 2011 Photographed by Tokyo Electric Power Company



(xv) Hydrant (G06)
August 25, 2011 Photographed by Tokyo Electric Power Company



(xvi) Vent valve of the water intake for the machine building
March 24, 2011 Photographed by Tokyo Electric Power Company



(xvii) Water intake for Unit 1
July 4, 2011 Photographed by Tokyo Electric Power Company




(xviii) Leaking point on the side pipeline stretching toward Units 5 and 6
August 15, 2011 Photographed by Tokyo Electric Power Company

* Of the entire outdoor fire extinguishing system, the pictures above show only examples of damage to facilities installed above ground.
(The condition of underground piping is yet to be confirmed.)


Photographs showing the installation of outdoor fire protection system facilities at the Fukushima Dai-ichi NPS




August 15, 2011 Photographed by Tokyo Electric Power Company



August 20, 2011 Photographed by Tokyo Electric Power Company



August 20, 2011 Photographed by Tokyo Electric Power Company



March 20, 2011 Photographed by Tokyo Electric Power Company

* Of the entire outdoor fire extinguishing system, the pictures above show only examples of damage to facilities installed above ground.
(The condition of underground piping is yet to be confirmed.)

Photographs showing the installation of fire hydrants in the T/Bs of Units 1 to 3

Unit 1 turbine building



August 25, 2011 Photographed by Tokyo Electric
Power Company

Hydrant (HB-9) on the
first floor



August 25, 2011 Photographed by Tokyo Electric
Power Company

Hydrant (HB-11) on the
first floor



August 25, 2011 Photographed by Tokyo Electric
Power Company

Hydrant (HB-18) on the
second floor

Photographs showing the installation of fire hydrants in the T/Bs of Units 1 to 3

Unit 2 turbine building



August 25, 2011 Photographed by Tokyo Electric
Power Company

Hydrant (FH-17) on the
second floor



August 25, 2011 Photographed by Tokyo Electric
Power Company

Hydrant (FH-18) on the
second floor



August 25, 2011 Photographed by Tokyo Electric
Power Company

Hydrant (FH-20) on the
second floor

Photographs showing the installation of fire hydrants in the T/Bs of Units 1 to 3

Unit 3 turbine building



August 25, 2011 Photographed by Tokyo Electric
Power Company

Hydrant (T-14) on the
first floor



August 25, 2011 Photographed by Tokyo Electric
Power Company


Hydrant (T-19) on the
second floor

Photographs showing damage to the main office building



March 29, 2011 Photographed by Tokyo Electric Power Company

Picture (i): Inside the office of the Public Relations Department on the first floor.



March 29, 2011 Photographed by Tokyo Electric Power Company

Picture (ii): Hallway near the entrance on the first floor.

Photographs showing damage to the main office building



May 6, 2011 Photographed by Tokyo Electric Power Company

Picture (iii): Inside the office of the General Affairs Department on the second floor.



March 29, 2011 Photographed by Tokyo Electric Power Company

Picture (iv): Inside the office of the General Engineering Department on the second floor.

Photographs showing damage to the main office building



May 6, 2011 Photographed by Tokyo Electric Power Company

Picture (v): Exterior of the main building.

Photographs showing damage to emergency access roads to the Fukushima Daiichi NPS




The lane on the sea side cracked parallel to the road and created a gap. The west side was passable.
Photographed by TEPCO on March 17, 2011



Although this area had had reinforcement work, cracks and gaps occurred on the sides of road which had not been reinforced.
Photographed by TEPCO on March 17, 2011



Although this is not an emergency access road, the slopes collapsed and blocked the road, leaving it impassable.
Photographed by TEPCO on March 20, 2011



Although there was no major damage to the road, a heavy oil tank washed in by the tsunami blocked the road, leaving it impassable.
Photographed by TEPCO on March 17, 2011



No particular problem was observed on the straight road stretching from the main gate.
Photographed by TEPCO on August 26, 2011




Although no particular problem was observed with the road, rubble scattered around due to the tsunami and explosion
Photographed by TEPCO on March 16, 2011



No particular problem was observed on the west sides of Units 1 to 4. When Units 1, 3 and 4 were damaged, rubble scattered around.
Photographed by TEPCO on March 20, 2011



Despite the scattering of some rubble, no particular problem was observed on the road.
Photographed by TEPCO on March 20, 2011



Based on data and documents by Tokyo Electric Power

Attachment II-29

Layout of the Emergency Response Office


Layout of the Emergency Response Office

(At the establishment of the Emergency Response Headquarters on March 11, 2011)

Meeting Rooms No.1 and No.2

The Restoration Team, Operation Team, Engineering Team and Health Physics Team (For Emergency Purpose)

* Actual layout may vary slightly depending on the situation




Information Gathering Room

Restoration Team (3)
(Maintenance Departments 1 & 2; Electrical Equipment Group: from the night of March 11)
(Maintenance Department 2, Reactor G/Turbine G: from the afternoon of March 15)
(General Affairs Department, Construction G: from March 16)

Attachment IV-1


Created by TEPCO

**Personnel Positioning of Seats
for Headquarters**
(At the establishment of the Emergency
Response Headquarters on March 11, 2011)




* Actual layout may vary slightly depending on the situation

Shift arrangements at the Fukushima Dai-ichi NPS



*1 A Senior Operator and a main-equipment shift operator work full time for each Unit.
*2 The number of shift members can vary depending on the situation at the Plant.


Layout of the main control room for Units 1 and 2



Attachment IV-3

Created by TEPCO


Isolation condenser (IC)



Created by TEPCO

Attachment IV-4

Unit 1 reactor pressure



- ① Scram by the earthquake at 14:46
- ② Pressure increase associated with the closing of the main steam isolation valve
- ③ Actuation of isolation condenser and associated pressure decrease at 14:52
- ④ Pressure increase associated with stoppage of the isolation condenser
- ⑤ Pressure fluctuation probably caused by the isolation condenser
- ※ It is estimated that the tsunami hit after 15:30. Recording probably stopped due to the impact of the tsunami.



Adopted from "The Impact of the Tohoku District – off the Pacific Ocean Earthquake on Nuclear Reactor Facilities at the Fukushima Dai-ichi Nuclear Power Station" (September, 2011) by TEPCO.

Illustrated overview of the safety relief valve (SRV) operating principle (safety valve function)


In times of normal operation

Explanation of the operating principle

- (i) The reactor pressure increases with the closing of the main steam isolation valve, etc.
- (ii) When the reactor pressure exceeds the set pressure of the safety valve (spring force), steam pushes the valve body of the SR valve up.
- (iii) A steam flow channel is formed after the valve body has been pushed up and the steam is released into the S/C through the exhaust pipe.




In the case of abnormal pressure increase




Compiled from documents by TEPCO

Attachment
IV-6

Illustrated overview of the safety relief valve (SRV) operating principle (in the case of relief valve actuation, ADS actuation or remote manual operation)



In times of normal operation



Explanation of the operating principle


The relief valve:

- (i) The reactor pressure increases with the closing of the main steam isolation valve, etc.
- (ii) When the reactor pressure reaches the set pressure of the relief valve, a signal is sent to the control solenoid valve in the nitrogen supply line.
- (iii) The flow channel is altered with the opening and closing of the control solenoid valve and nitrogen gas is fed into the SR valve cylinder.
- (iv) When nitrogen gas is fed into the cylinder, the piston and the stem are pushed up by the coupling lever.
- (v) The valve body is then in a free state after the stem has been pushed up. When the valve body is pushed up by the steam pressure in this state, a steam flow channel is formed and steam is released into the S/C through the exhaust pipe.

***In the case of ADS, an actuation signal is sent when there is a loss of coolant accident (LOCA) instead of procedures (i) and (ii), but the following procedures, (iii) to (v), are the same.**


*** In the case of remote manual control, an actuation signal is sent according to manual control from the main control room instead of procedures (i) and (ii), but the following procedures, (iii) to (v), are the same.**

In the case of abnormal pressure increase, loss of coolant accident or remote manual control



Compiled from documents by TEPCO


Layout of the Main Control Room for Units 3 and 4



Attachment IV-7


Prepared by TEPCO

Unit 1 reactor water level



Green = reactor water level


Red = reactor water level (fuel range)



- ① Scram due to the earthquake at 14:46 (Fast-forwarding of chart: 60 times faster, a minute for an hour)
- ② Loss of power and closing of the main steam isolation valve around this time (Fast-forwarding of chart reset by the loss of power)
- ③ Automatic startup of the isolation condenser
- ④ Possible fluctuation of water level due to the operation of the isolation condenser


Extracted from "The Impact of the Tohoku District – off the Pacific Ocean Earthquake on Nuclear Reactor Facilities at the Fukushima Dai-ichi Nuclear Power Station" (September, 2011) by TEPCO

Unit 1 reactor recirculation pump inlet temperature



- ① Scram due to the earthquake at 14:46
- ② Decrease in power due to the scram, pressure decrease due to the operation of the isolation condenser and decrease in temperature due to the injection of low-temperature
- ③ Shutdown of the isolation condenser that automatically started

Illustrated overview of reactor core isolation by the IC system (closing of the isolation valve)



The DG Breaker ON/OFF status and IC operation status
as recorded on the Unit 1 alarm typewriter

1447	B033	CAMS	H2	MONI	S/C	LOW	RSN	
14	47	57	070	D590	DIES GEN CB	1D-1	ON	
1447	B034	CAMS	Q2	MONI	S/C	LOW	RSN	
14	47	57	140	D681	6.9KV BUS VLT	1D	LOS	OFF
1447	G000	GENERATR	GROS	LOAD	383.0	MW	NORMAL	RETURN
14	47	58	920	D589	DIES GEN CB	1C-1	ON	
1447	G001	GENERATR	GROS	VAR	9.0<	10.0	MVAR	
14	47	58	970	D680	6.9KV BUS VLT	1C	LOS	OFF
1447	G002	GENERATR	VOLT				LOW	RSN
14	48	00	220	D660	PLR A LOCOUT	RY	ACT	ON
1447	C007	REAC	PMP	TOTL	FLOW		LOW	RSN
14	48	13	280	D576	TURBINE	VIB	OVER	NORM

D/G 1B breaker on


D/G 1A breaker on

1452	A567	RX	MODE	SW	REFUEL	OFF	
1452	C020	SUPPRESSION	LEVL	16.8	MM	NORMAL	RETURN
1452	C020	SUPPRESSION	LEVL	37.6>	20.0	MM	
1452	B526	ISO-CON	VLV	B	OPN	ON	
1452	B525	ISO-CON	VLV	A	OPN	ON	
1452	C020	SUPPRESSION	LEVL	14.0	MM	NORMAL	RETURN
1452	A516	SRM	DET	POS	IN		
1452	C020	SUPPRESSION	LEVL	35.2>	20.0	MM	

IC operation


Adopted from "The Impact of the Tohoku District – of the Pacific Ocean Earthquake on Nuclear Reactor Facilities at the Fukushima Dai-ichi Nuclear Power Station" (September, 2011) by TEPCO.

Illustrated overview of reactor water levels




Created by TEPCO

Conceptual diagram of alternative water injection facilities (Unit 1)




Conceptual diagram of alternative water injection facilities (Units 2 to 5)




Compiled from the "Report on Preparation for Accident Management" (May, 2002) by TEPCO

Overview of water injection by fire engines (at around 05:46 on March 12)



Overview of water injection by fire engines (after around 10:52 on March 12)



Compiled from documents by TEPCO

Examples of protective outfits and gears used



General work uniform
Level B gloves,
Level B shoes,
Level B helmet



Level B clothing
Level B gloves,
Level B shoes,
Level B helmet



Level B clothing
Level B gloves,
thin latex gloves,
Level B2 shoes,
Level B helmet



Level C clothing
thin latex gloves,
Level C headwear,
Level C socks



Level C clothing
thin latex gloves,
Level C headwear,
Level C socks,
Level C shoes,
Level C helmet
(Level C gloves, if necessary)



Two-piece anorak




Full face mask



Hood mask



Adopted from "The Impact of the Tohoku District – off the Pacific Ocean Earthquake on Nuclear Reactor Facilities at the Fukushima Dai-ichi Nuclear Power Station" (September, 2011) by TEPCO.

Unit 1 vent line




Attachment IV-17

Illustrated overview of the operating principle of air-operated (AO) valves



Compiled from documents by TEPCO


Overview of water injection by fire engines (at around 19:04 on March 12)



Attachment IV-19

Compiled from documents by TEPCO

Overview of water injection by fire engines (at around 07:00 on March 13)




*The blue dotted lines show that water injection had not started by around 07:00 on March 13.

Compiled from documents by TEPCO

Attachment IV-20

Overview of water injection by fire engines (at around 09:00 on March 13)




*The blue dotted lines show that water injection had not started by around 09:00 on March 13.

Compiled from documents by TEPCO

Attachment IV-21


Overview of water injection by fire engines (the early evening of March 13)



*The blue dotted lines show that water injection had not started by the early evening of March 13.

Compiled from documents by TEPCO

Overview of water injection by fire engines (until around 11:01 on March 14)




*The water injection lines to Unit 2 were changed from blue dotted lines to green before the explosion at Unit 3, but water injection had not started yet.

Compiled from documents by TEPCO


Attachment IV-23

Unit 2 vent line



Attachment IV-24


Unit 3 vent line



Rupture disc bursting pressure: 427 kPa [gage]


Attachment IV-25

**Sectional view of the Unit 4
spent fuel pool and nearby facilities**



Attachment IV-26

Overview of water injection by fire engines (at around 14:43 on March 14)




*The blue dotted lines show that water injection had not started by around 14:43 on March 13.

Compiled from documents by TEPCO

Attachment IV-27

Comparative review of the chosen methods for depressurization and alternative water injection of Unit 2



Opinion of Site Superintendent, Mr. Yoshida

Concern:

Because of high pool temperature and pressure in the Unit 2 S/C uncondensed, steam through the SRV might lead to not only insufficient depressurization of the reactor but also damage of the S/C.

Proposal:

Water should be injected, depressurizing the RPV, after configuring an S/C vent line to secure an escape route for S/C pressure.

Opinion of Chairman, Madarame


Concern:

Because of no water injection into Unit 2 for a long time, there is a possibility that the RPV would be damaged due to possible fuel damage.

Proposal:

Water injection should come first, depressurizing the RPV without waiting for the completion of an S/C vent line.

Overview of water injection by fire engines (after around 19:57 on March 14)




*The green dotted lines show that water was injected temporarily.

Compiled from documents by TEPCO


Attachment IV-29

Overview of water injection by fire engines (at around 20:30 on March 14)




Compiled from documents by TEPCO

Pool gate configuration



Water level changes of the spent fuel pool after the accident (before water injection started)



Compiled from "The Impact of the Tohoku District – off the Pacific Ocean Earthquake on Nuclear Reactor Facilities at the Fukushima Dai-ichi Nuclear Power Station" (September, 2011) by TEPCO.

Progress in the cooling of spent fuel pools

Blue: Water spray by helicopters, water cannon trucks, fire engines and concrete pumping trucks
 Green: Water injection from the fuel pool cooling & clean-up system (FPC)
 Purple: Water injection by temporary water injection systems
 Red: Cooling by alternative cooling systems

Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
Mar/17			9:48 - 10:01 Water sprinkle by the Self-Defense Force (Helicopters) [Approximately 30t / Seawater] 19:05 - 19:13 Water spray by the Tokyo Police Department (Water cannon trucks) [Approximately 44t / Seawater] 19:35 - 20:09 Water spray by the Self-Defense Forces (Fire Engines) [Approximately 30t / Fresh Water]			
Mar/18			14:00 - 14:38 Water spray by the Self-Defense Force (Fire Engines) [Approximately 40t / Fresh Water] 14:42 - 14:45 Water spray by TEPCO (High Pressure Water cannon truck of US forces) [approximately 2t / Fresh Water]			
Mar/19			0:30 - 1:10 Water spray by the Tokyo Fire Department (Fire Engines) [Approximately 60t / Seawater] 14:10 - 3/20 3:40 Water spray by the Tokyo fire Department ((Fire Engines) [Approximately 2430t / Seawater]		1:55 Startup of Temporary Residual Heat Removal Service Water System (RHRS) 5:00 Start of Cooling in the Fuel Pool Cooling mode of the Residual Heat Removal System (RHR)	21:16 Startup of Temporary Residual Heat Removal Service Water System (RHRS) 22:14 Start of Cooling in the Fuel Pool Cooling mode of the Residual Heat Removal System (RHR)
Mar/20		15:05 - 19:45 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 40t / Seawater]	21:36 - 3/21 3:58 Water spray by the Tokyo Fire Department (Fire Engines) [Approximately 1137t / Seawater]	8:21 - 9:40 Water spray by the Self-Defense Force (Fire Engines) [Approximately 80t / Fresh Water] 18:30 - 19:46 Water spray by the Self-Defense Force (Fire Engines) [Approximately 80t / Fresh Water]	Cooling by Temporary	Cooling by Temporary

Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
Mar/21				6:37 - 8:41 Water spray by the Self-Defense Force (Fire Engines, High Pressure Water cannon truck of US forces) [Approximately 92t / Fresh Water]	Residual Heat Removal System (RHR)	Residual Heat Removal System (RHR)
Mar/22		16:07 - 17:01 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 18 t / Seawater]	15:10 - 15:59 Water spray by Tokyo Fire Department and Osaka-City Fire Department (Fire Engines) [Approximately 150t / Seawater]	17:17 - 20:32 Water spray by concrete pumping trucks [Approximately 150t / Seawater]		
Mar/23			11:03 - 13:20 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 35 t / Seawater]	10:00 - 13:02 Water spray by concrete pumping trucks [Approximately 125t / Seawater]		
Mar/24			5:35 - 16:05 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 120 t / Seawater]	14:36 - 17:30 Water spray by concrete pumping trucks [Approximately 150t / Seawater]		
Mar/25		10:30 - 12:19 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 30 t / Seawater]	13:28 - 16:00 Water spray by Kawasaki City Fire Department (Fire Engines) [Approximately 450 t / Seawater]	6:05 - 10:20 Water spray from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 21t / Seawater] 19:05 - 22:07 Water spray by concrete pumping trucks [Approximately 150t / Seawater]		
Mar/26						
Mar/27			12:34 - 14:36 Water spray by concrete pumping trucks [Approximately 100t / Seawater]	16:55 - 19:25 Water spray by concrete pumping trucks [Approximately 125t / Seawater]		
Mar/28						
Mar/29		16:30 - 18:25 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 15 - 30 t / Fresh Water]	14:17 - 18:18 Water spray by concrete pumping trucks [Approximately 100t / Fresh Water]			
Mar/30		19:05 - 23:50 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Less than 20 t / Fresh Water]		14:04 - 18:33 Water spray by concrete pumping trucks [Approximately 140t / Fresh Water]		
Mar/31	13:03 - 16:04 Water spray by concrete pumping trucks [Approximately 90 t / Fresh Water]		16:30 - 19:33 Water spray by concrete pumping trucks [Approximately 105t / Fresh Water]			
Apr/1		14:56 - 17:05 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 70 t / Fresh Water]		8:28 - 14:14 Water spray by concrete pumping trucks [Approximately 180t / Fresh Water]		
Apr/2			9:52 - 12:54 Water spray by concrete pumping trucks [Approximately 75 t / Fresh Water]			
Apr/3				17:14 - 22:16 Water spray by concrete pumping trucks [Approximately 180 t / Fresh Water]		

Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
Apr/4		11:05 - 13:37 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 70 t / Fresh Water]	17:03 - 19:19 Water spray by concrete pumping trucks [Approximately 70 t / Fresh Water]			
Apr/5				17:35 - 18:22 Water spray by concrete pumping trucks [Approximately 20 t / Fresh Water]		
Apr/6						
Apr/7		13:29 - 14:34 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 36 t / Fresh Water]	6:53 - 8:53 Water spray by concrete pumping trucks [Approximately 70 t / Fresh Water]	18:23 - 19:40 Water spray by concrete pumping trucks [Approximately 38 t / Fresh Water]		
Apr/8			17:06 - 20:00 Water spray by concrete pumping trucks [Approximately 75 t / Fresh Water]			
Apr/9				17:07 - 19:24 Water spray by concrete pumping trucks [Approximately 90 t / Fresh Water]		
Apr/10		10:37 - 12:38 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 60 t / Fresh Water]	17:15 - 19:15 Water spray by concrete pumping trucks [Approximately 80 t / Fresh Water]			
Apr/11						
Apr/12			16:26 - 17:16 Water spray by concrete pumping trucks [Approximately 35 t / Fresh Water]			
Apr/13		13:15 - 14:55 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 60 t / Fresh Water]		0:30 - 6:57 Water spray by concrete pumping trucks [Approximately 195 t / Fresh Water]		
Apr/14			15:56 - 16:32 Water spray by concrete pumping trucks [Approximately 25 t / Fresh Water]			
Apr/15				14:30 - 18:29 Water spray by concrete pumping trucks [Approximately 140 t / Fresh Water]		
Apr/16		10:13 - 11:54 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 45 t / Fresh Water]				
Apr/17				17:39 - 21:22 Water spray by concrete pumping trucks [Approximately 140 t / Fresh Water]		
Apr/18			14:17 - 15:02 Water spray by concrete pumping trucks [Approximately 30 t / Fresh Water]			
Apr/19		16:08 - 17:28 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 47 t / Fresh Water]		10:17 - 11:35 Water spray by concrete pumping trucks [Approximately 40 t / Fresh Water]		

Cooling by Temporary Residual Heat Removal System (RHR)

Cooling by Temporary Residual Heat Removal System (RHR)

Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
Apr/20				17:08 - 20:31 Water spray by concrete pumping trucks [Approximately 100 t / Fresh Water]		
Apr/21				17:14 - 21:20 Water spray by concrete pumping trucks [Approximately 140 t / Fresh Water]		
Apr/22		15:55 - 17:40 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 50 t / Fresh Water]	14:19 - 15:40 Water spray by concrete pumping trucks [Approximately 50 t / Fresh Water]	17:52 - 23:53 Water spray by concrete pumping trucks [Approximately 200 t / Fresh Water]		
Apr/23				12:30 - 16:44 Water spray by concrete pumping trucks [Approximately 140 t / Fresh Water]		
Apr/24				12:25 - 17:07 Water spray by concrete pumping trucks [Approximately 165 t / Fresh Water]		
Apr/25		10:12 - 11:18 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 38 t / Fresh Water]		18:15 - 4/26 0:26 Water spray by concrete pumping trucks [Approximately 210 t / Fresh Water]		
Apr/26			12:25 - 14:02 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 47.5 t / Fresh Water]	16:50 - 20:35 Water spray by concrete pumping trucks [Approximately 130 t / Fresh Water]		
Apr/27				12:18 - 15:15 Water spray by concrete pumping trucks [Approximately 85 t / Fresh Water]		
Apr/28		10:15 - 11:28 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 43 t / Fresh Water]			Cooling by Temporary Residual Heat Removal System (RHR)	Cooling by Temporary Residual Heat Removal System (RHR)
Apr/29						
Apr/30						
May/1						
May/2		10:05 - 11:40 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 55 t / Fresh Water]				
May/3						
May/4						
May/5				12:19 - 20:46 Water spray by concrete pumping trucks [Approximately 270 t / Fresh Water]		
May/6		9:36 - 11:16 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 58 t / Fresh Water]		12:38 - 17:51 Water spray by concrete pumping trucks [Approximately 180 t / Fresh Water]		
May/7				14:05 - 17:30 Water spray by concrete pumping trucks [Approximately 120 t / Fresh Water]		

Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
May/8			12:10 - 14:10 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 60 t / Fresh Water]			
May/9			12:14 - 15:00 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 80 t / Fresh Water]	16:05 - 19:05 Water spray by concrete pumping trucks [Approximately 100 t / Fresh Water]		
May/10		13:09 - 14:45 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 56 t / Fresh Water]				
May/11				16:07 - 19:38 Water spray by concrete pumping trucks [Approximately 120 t / Fresh Water]		
May/12						
May/13				16:04 - 19:04 Water spray by concrete pumping trucks [Approximately 100 t / Fresh Water]		
May/14		13:00 - 14:37 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 56 t / Fresh Water]				
May/15				16:25 - 20:25 Water spray by concrete pumping trucks [Approximately 140 t / Fresh Water]		
May/16			15:00 - 18:32 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 106 t / Fresh Water]			
May/17				16:14 - 20:06 Water spray by concrete pumping trucks [Approximately 120 t / Fresh Water]		
May/18		13:10 - 14:40 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 53 t / Fresh Water]				
May/19				16:30 - 19:30 Water spray by concrete pumping trucks [Approximately 100 t / Fresh Water]		
May/20	15:06 - 16:15 Water spray by concrete pumping trucks [Approximately 60 t / Fresh Water]					
May/21				16:00 - 19:56 Water spray by concrete pumping trucks [Approximately 130 t / Fresh Water]		
May/22	15:33 - 17:09 Water spray by concrete pumping trucks [Approximately 90 t / Fresh Water]	13:02 - 14:40 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 56 t / Fresh Water]				

Cooling by Temporary Residual Heat Removal System (I)

Cooling by Temporary Residual Heat Removal System (I)


Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
May/23				16:00 - 19:09 Water spray by concrete pumping trucks [Approximately 100 t / Fresh Water]	RHR	RHR
May/24			10:15 - 13:35 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 100 t / Fresh Water]			
May/25				16:36 - 20:04 Water spray by concrete pumping trucks [Approximately 121 t / Fresh Water]		
May/26		10:06 - 11:36 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 53 t / Fresh Water]				
May/27				17:05 - 20:00 Water spray by concrete pumping trucks [Approximately 100 t / Fresh Water]		
May/28	16:47 - 17:00 Leak Test of the Fuel Pool Cooling & Clean-up System (FPC) Line [Approximately 5t / Fresh Water]		13:28 - 15:08 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 50 t / Fresh Water]	17:56 - 19:45 Water spray by concrete pumping trucks [Approximately 60 t / Fresh Water]	21:14 One of the pumps of the temporary Residual Heat Removal Service Water System (RHRS) stopped.	
May/29	11:10 - 15:35 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 168 t / Fresh Water]				12:31 The temporary Residual Heat Removal Service Water System (RHRS) Pump restored and Started up	
May/30		12:06 - 13:52 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 53 t / Fresh Water]				
May/31		17:21 - Start of Cooling by Alternative Cooling System				
Jun/1		5:06 - 7:06 Sirculation cooling system pump stopped 6:06 - 6:53 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 25t / Fresh Water] 7:06 - Resumed of Cooling by Alternative Cooling System	14:34 - 15:54 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 40t / Fresh Water]			
Jun/2						
Jun/3				14:35 - 21:15 Water spray by concrete pumping trucks [Approximately 210 t / Fresh Water]		
Jun/4				14:23 - 19:45 Water spray by concrete pumping trucks [Approximately 180 t / Fresh Water]		
Jun/5	10:16 - 10:48 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 15 t / Fresh Water]		13:08 - 15:14 Water injection from the Fuel Pool Cooling & Clean-up System (FPC) [Approximately 60 t / Fresh Water]			

Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
Jun/6				15:56 - 18:35 Water spray by concrete pumping trucks [Approximately 90 t / Fresh Water]		
Jun/7						
Jun/8				16:12 - 19:41 Water spray by concrete pumping trucks [Approximately 120 t / Fresh Water]		
Jun/9			13:42 - 15:31 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 55 t / Fresh Water]			
Jun/10						
Jun/11						
Jun/12						
Jun/13			10:09 - 11:48 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 42 t / Fresh Water]	16:36 - 21:00 Water spray by concrete pumping trucks [Approximately 150 t / Fresh Water]		
Jun/14				16:10 - 20:52 Water spray by concrete pumping trucks [Approximately 150 t / Fresh Water]		
Jun/15						
Jun/16				13:14 - 15:44 Water injection by temporary water injection system [Approximately 75t / Fresh Water]		
Jun/17			10:19 - 11:57 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 49 t / Fresh Water]			
Jun/18				16:05 - 19:23 Water injection by temporary water injection system [Approximately 99t / Fresh Water]		
Jun/19						
Jun/20						
Jun/21						
Jun/22				14:31 - 16:38 Water injection by temporary water injection system [Approximately 56t / Fresh Water]		
Jun/23						
Jun/24						
Jun/25						
Jun/26			9:56 - 11:23 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 45 t / Fresh Water]			
Jun/27			15:00 - 17:18 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 60 t / Fresh Water]			
Jun/28						

Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
Jun/29			14:45 - 15:53 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 30 t / Fresh Water]	11:47 - 12:01 Water injection by temporary water injection system [Approximately 7t / Fresh Water]		
Jun/30			19:47 Start of Cooling by Alternative Cooling system	11:30 - 11:55 Water injection by temporary water injection system [Approximately 13t / Fresh Water]		
Jul/1						
Jul/2						
Jul/3						
Jul/4						
Jul/5	15:10 - 17:30 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 75 t / Fresh Water]					
Jul/6						
Jul/7						
Jul/8						
Jul/9						
Jul/10						
Jul/11						
Jul/12						
Jul/13						
Jul/14						
Jul/15						
Jul/16						
Jul/17						
Jul/18						
Jul/19						
Jul/20						
Jul/21						
Jul/22						
Jul/23						
Jul/24						
Jul/25						
Jul/26						
Jul/27						
Jul/28						
Jul/29						
Jul/30						
Jul/31				8:47 - 9:38 Water injection by temporary water injection system [Approximately 25t / Fresh Water] 12:44 Start of Cooling by Alternative Cooling System		
Aug/1						
Aug/2						
Aug/3						
Aug/4						

Date	Unit 1 Pool	Unit 2 Pool	Unit 3 Pool	Unit 4 Pool	Unit 5 Pool	Unit 6 Pool
Aug/5	15:20 - 17:51 Water injection from the Fuel Pool Cooling & Clean- up System (FPC) [Approximately 75 t / Fresh Water]					
Aug/6						
Aug/7						
Aug/8						
Aug/9						
Aug/10	11:22 Start of Cooling by Alternative Cooling System					
Aug/11						
Aug/12						
Aug/13						
Aug/14						
Aug/15						
Aug/16						
Aug/17						
Aug/18						
Aug/19						
Aug/20						
Aug/21						
Aug/22						
Aug/23						
Aug/24						
Aug/25						
Aug/26						
Aug/27						
Aug/28						
Aug/29						
Aug/30						
Aug/31						


Water injection into the Unit 2 spent fuel pool using the FPC System




Attachment IV-33

Created by TEPCO

Skimmer surge tank configuration




Water injection into the spent fuel pools of Units 3 and 4 using the FPC System



Attachment IV-35

Created by TEPCO


Alternative cooling system for the Unit 2 spent fuel pool



Created by TEPCO


Attachment IV-36

Alternative cooling system for the Unit 3 spent fuel pool



Created by TEPCO


Water injection into the Unit 1 spent fuel pool using the FPC system



Created by TEPCO


Attachment IV-38

Temporary SFP water injection system (“Mizuha”)



Adopted from “Progress Status of Roadmap towards Restoration after the Accident at the Fukushima Daiichi Nuclear Power Station, TEPCO” (September, 2009)

Water injection into the Unit 4 spent fuel pool using the ICM tubes




* The ICM tubes are stainless steel tubes housings installed within and welded to the reactor pressure vessel to protect the In-Core Monitors (ICMs) that measure neutron flux in the reactor.

Compiled from documents by TEPCO


Attachment IV-40

Alternative cooling system for the Unit 1 spent fuel pool



Attachment IV-41


Alternative cooling system for the Unit 4 spent fuel pool



Attachment IV-42

Created by TEPCO


Cooling system for the Unit 5 spent fuel pool



Attachment IV-43

Created by TEPCO

Cooling system for the Unit 6 spent fuel pool




Attachment IV-44

Created by TEPCO

This page intentionally left blank.

Geographical overview of the restricted area, deliberate evacuation areas, areas prepared for emergency evacuation and regions including specific spots from where evacuation is recommended (before the cancellation of areas prepared for emergency evacuation)


Attachment V-1



Data supplied by the Nuclear Emergency Response Headquarters



Geographical overview of the restricted area, deliberate evacuation areas, areas prepared for emergency evacuation and regions including specific spots from where evacuation is recommended (after the cancellation of areas prepared for emergency evacuation)

Attachment V-2



Data supplied by the Nuclear Emergency Response Headquarters

Overview of the penetration of groundwater into the basement of Unit 6 buildings




Based on data supplied by TEPCO.

Attachment V-3

Photographs showing the penetration of water into the MC room (as of March 26)

Attachment V-4



(Photo by TEPCO on Aug 22)



(Photo by TEPCO on Mar 26)


Close up



(Photo by TEPCO on Mar 26)



(Photo by TEPCO on Aug 22)




(Photo by TEPCO on Aug 22)



(Photo by TEPCO on Aug 22)

Prepared by TEPCO.


Overview of efforts to supply power from Unit 6 to Unit 5 (as of March 21)



Based on data supplied by TEPCO.


Attachment V-5

Overview of water that remained in the second basement area of the Unit 6 R/B and RW/B



Configuration and layout of the subdrain system


Attachment V-7



Available opening: approx.
450mm × approx. 700mm


(All five photos were taken by TEPCO on May 2 in subdrain No. 56 located in the southeast of the Unit 4 T/B)

Layout of the subdrain in Units 5 & 6



Prepared by TEPCO.


Highly contaminated water outflow routes near the Unit 2 water intake (plane view)



Attachment
V-8

Prepared by TEPCO.

Highly contaminated water outflow routes near the Unit 2 water intake (sketch)



Prepared by TEPCO.

Attachment V-9

Response to the outflow of highly contaminated water near the Unit 2 water intake (status at the time of detection)






Photo of outflow (taken by TEPCO at approximately 12:40 on April 2)


B-B Section



A-A Section




C-C Section



Prepared by TEPCO.


Attachment V-10

Response to the outflow of highly contaminated water near the Unit 2 water intake (status after the injection of concrete)




Attachment V-11


Response to the outflow of highly contaminated water near the Unit 2 water intake (status after the injection of polymer, etc.)



Response to the outflow of highly contaminated water near the Unit 2 water intake (status after the injection of water glass-based chemical solution) - (1)




Response to the outflow of highly contaminated water near the Unit 2 water intake (status after the injection of water glass-based chemical solution) - (2)



Based on materials supplied by TEPCO.

Enhanced measures for preventing the spread of radioactive water (bird's eye view of the sites where measures were implemented)



Enhanced measures for preventing the spread of radioactive water (list)

Attachment V-16

No.	Measure	Period	Overview	Condition
1	Installation of large sandbags	April 5 - 8	Sixty-two large sandbags piled up on the damaged area of the breakwaters (outlying facilities).	
2	Installation of silt fences	April 11 - 14	Silt fences spread out in six locations: the water intake curtain wall, in front of the screen pump rooms, and the damaged area of the penetration resistant structures.	 
3	Installation of steel panels	April 12 - 15	Seven steel panels installed in front of the screen pump room of Unit 2.	
4	Submersion of sandbags containing zeolite	April 15 and 17, May 19 (additional submersion)	Sandbags containing zeolite submerged in front of the seawall between the screen pump rooms of each Unit.	
5	Closure of pits and other routes	<ul style="list-style-type: none"> - Closure of pits with seawater pipe trench: April 5 - May 30 - Closure of pits with power supply cable trench and other routes: April 2 - June 25 (including countermeasures against leakage of contaminated water in Unit 2) 	<p>Water blocking measures implemented in the following pits and locations where there was a risk of leakage of radioactive solution:</p> <ul style="list-style-type: none"> - Closure of pits with seawater pipe trench - Closure of power supply cable trench 	
6	Installation of seawater circulation clean-up device	<p>Installation: mid – late May</p> <p>Operation: June 13</p>	Seawater circulation clean-up device that uses zeolite as an absorbent installed on the seawall between the screen pump rooms of Units 2 and 3. Seawater clean-up is currently being conducted.	 
7	Installation of flashboards in front of the screen rooms	June 12 - 29	Steel flashboards installed on the sea side of the screen pump rooms.	
8	Insertion of steel pipe sheet piles around outlying facilities	July 12 - September 28	Steel pipe sheet piles and the other members inserted inside large sandbags piled up on the damaged area of the breakwaters (outlying facilities).	

Prepared by TEPCO.

Level of contaminated water in the Unit 3 T/B (in the pit)

Unit: mm


Date	Mar. 28			Mar. 29			Mar. 30			Mar. 31	
Time	8:30	13:00	18:00	9:00	12:00	15:00	7:00	14:00	18:00	10:10	12:10
Unit 3 pit water level (O.P.)	2,450	2,450	2,350	2,450	2,450	2,450	2,450	2,450	2,450	2,450	2,450
Unit 3 T/B B1 water level (O.P.)	2,490										
Unit 4 T/B B1 water level (O.P.)		2,420				2,420		2,420			2,420

Unit: mm

Date	Apr. 01	Apr. 02	Apr. 03	Apr. 04		Apr. 05			Apr. 06		
Time	11:00	11:00	11:00	8:00	11:00	7:00	11:00	19:00	7:00	9:00	20:30
Unit 3 pit water level (O.P.)	2,450	2,450	2,550	2,700	2,750	2,740	2,740	2,740	2,740	2,740	2,740
Unit 3 T/B B1 water level (O.P.)											
Unit 4 T/B B1 water level (O.P.)					2,850		2,800			2,800	


Unit: mm

Date	Apr. 07			Apr. 08			Apr. 09			Apr. 10		
Time	7:00	11:00	18:00	7:00	11:00	18:30	7:00	11:00	18:00	7:00	11:00	18:00
Unit 3 pit water level (O.P.)	2,740	2,740	2,740	2,740	2,740	2,750	2,750	2,750	2,770	2,770		2,780
Unit 3 T/B B1 water level (O.P.)											2,900	2,900
Unit 4 T/B B1 water level (O.P.)		2,800			2,800			2,800			2,800	



Based on data supplied by TEPCO.


Highly contaminated water outflow routes near the Unit 3 water intake (birds eye view)



Attachment V-18

Prepared by TEPCO.


Highly contaminated water outflow routes near the Unit 3 water intake (sketch)




Attachment V-19

Prepared by TEPCO.

Response to the outflow of highly contaminated water near the Unit 3 water intake



A-A cross section



Water leakage from the power supply cable pit to the screen area (photo by TEPCO at 18:30 on May 11)



Above: water flow to the power supply cable pit (photo by TEPCO at 10:30 on May 11)
Below: after concrete injected into the pit where leakage found (photos by TEPCO at 17:30 on May 12) Prepared by TEPCO.

Attachment V-20

The International Nuclear and Radiological Event Scale

(“INES”) at nuclear facilities and installations

INES LEVEL		Criteria on people and the environment	Criteria on radiological barriers and control		Criteria on Defense-in-Depth	
ACCIDENT	LEVEL 7 (MAJOR ACCIDENT)	- Major release of radioactive material with widespread health and environmental effects requiring implementation of planned and extended countermeasures.. (An atmospheric release of radioactive material equivalent to more than tens of thousands of terabecquerels of iodine-131).	Chernobyl NPP, USSR (now in Ukraine 1986			
	LEVEL 6 (SERIOUS ACCIDENT)	- Significant release of radioactive material likely to require implementation of planned countermeasures. (An atmospheric release of radioactive material equivalent to the order of thousands to tens of thousands of terabecquerels of iodine-131).				
	LEVEL 5 (ACCIDENT WITH WIDER CONSEQUENCES)	- A limited release of radioactive material likely to require implementation of some planned countermeasures. - Several deaths from radiation. (An atmospheric release of radioactive material equivalent to the order of hundreds to thousands of terabecquerels of iodine-131).	Windscale Pile, UK (1957)	- Severe damage to reactor core (meltdown of more than several percent of fuel, or a release of radioactive material from the fuel bundles equivalent to more than several percent of the reactor core inventory) - Release of large quantities of radioactive material within an installation with a high probability of significant public exposure. This could arise from a major critical accident or fire.	Three Mile Island, NPP, USA (1979)	
	LEVEL 4 (ACCIDENT WITH LOCAL CONSEQUENCES)	- Minor release of radioactive material unlikely to result in implementation of planned countermeasures other than local food controls. - At least one death from radiation. ((An atmospheric release of radioactive material equivalent to the order of tens to hundreds of terabecquerels of iodine-131).	JCO critical accident (1999)	- Meltdown of or damage to fuel resulting in a release of radioactive material of more than 0.1% of the fuel bundles. - Release of large quantities of radioactive material within an installation with a high probability of significant public exposure.	Saint-Laur ent NPP, France, (1980)	

INCIDENT	LEVEL 3 (SERIOUS INCIDENT)	<ul style="list-style-type: none"> - Exposure in excess of ten times the statutory annual limit for workers. - Non-lethal deterministic health effect (e.g. burns) from radiation. 		<ul style="list-style-type: none"> - Exposure rates of more than 1 Sv/h in an operating area. - Severe contamination in an area not expected by design, with a low probability of significant public exposure. 		<ul style="list-style-type: none"> - Near accident at a nuclear power plant with no safety provisions remaining. - Lost or stolen highly radioactive sealed source. - Misdellivered highly radioactive sealed source without adequate procedures in place to handle it. 	Fire incident in Vandellos NPP, Spain (1989)
	LEVEL 2 (INCIDENT)	<ul style="list-style-type: none"> - Exposure of a member of the public to more than 10 mSv. - Exposure of a worker to more than the statutory annual limit. 		<ul style="list-style-type: none"> - Radiation levels in an operating area of more than 50 mSv/h. - Significant contamination within the facility into an area not expected by design. 		<ul style="list-style-type: none"> - Significant failures in safety provisions but with no actual consequences. - Found highly radioactive sealed orphan source, device or transport package found with safety provisions intact. - Inadequate packaging of a highly radioactive sealed source. 	Accident involving broken steam generator heat transfer tube at Mihama No.2 plant, Japan (1991)
	LEVEL 1 (ANOMALY)					<ul style="list-style-type: none"> - Overexposure of a member of the public to more than the statutory annual limits. - Minor problems with safety components with significant defense-in-depth remaining. - Low activity lost or stolen radioactive source, device or transport package. 	"Monju" sodium leakage incident, Japan (1995), etc.
	No Safety Significance (Below Scale / Level 0)						

Based on the "International Nuclear Event Scale" prepared by the Nuclear and Industrial Safety Agency

“Report on the results of the seismic response analysis of the reactor building and equipment, and piping systems, which are important for seismic safety, of the Fukushima Daiichi Nuclear Power Station Unit No.2, using the seismic records observed at the 2011 Tohoku District - off the Pacific Ocean Earthquake (Outline)” dated June 17, 2011 and prepared by Tokyo Electric Power Company (Abstract)

1. (Dispensed)

2. Reactor building

To establish the condition of the reactor building during the earthquake, the seismic response analysis of the reactor building of Fukushima Daiichi Nuclear Power Station Unit No. 2 based on the 2011 Tohoku District - off the Pacific Ocean Earthquake was conducted using seismic records observed at the base mat of the building.

In the seismic response analysis, a model that could adequately represent the characteristics of the building and structures, and the ground was created (Fig. 1).

As a result of the seismic response analysis, the maximum shearing strain on the seismic-resistant walls was 0.43×10^{-3} (in the east-west direction, 5th floor), and it was confirmed that all seismic-resistant walls other than the one in the east-west direction on the 5th floor showed stress and distortion to the same or lesser extent than those of the first flexion point of the Skelton curve (Fig. 2, 3).




Fig. 1. Unit 2 Reactor Building (Model)




Fig. 2. Shearing Strain on the Seismic-resistant Walls
(north-south direction)




Fig. 3. Shearing Strain on the Seismic-resistant Walls
(east-west direction)



3. Equipment and piping systems important to seismic safety

The seismic response analysis based on seismic records observed of the Tohoku District - off the Pacific Ocean Earthquake was conducted on large components such as the reactor of the Fukushima Daiichi Nuclear Power Station Unit No. 2, and a comparison was made between the resulting seismic loads, etc. and those already obtained through the seismic safety evaluation with past reference seismic motion, Ss.

As a result of the comparison, the seismic loads, etc. due to the Earthquake partly exceeded those obtained through the seismic safety evaluation. However, through the seismic assessment of the main facilities that had functions important to safety related to the “shutdown” and “cooling” of the reactor and “confinement” of radioactive substances, it was confirmed that the calculated stress and others were below the evaluation criteria (Table-1). From the results, it is estimated that the main facilities that have functions important to safety were able to maintain the safety functions at the time of and right after the earthquake.

**Table 1. Summary of the impact assessment on equipment and piping systems important to seismic safety
(Fukushima Daiichi Nuclear Power Station Unit 2)**

Equipment, etc.		Seismic response load	Reference seismic motion, Ss	Results of Simulation analysis	Seismic assessment results
Seismic load, etc.	Reactor pressure vessel base	Shearing force (kN)	4960	5110	Reactor pressure vessel (foundation bolt) Calculated value: 29 MPa Evaluation criteria: 222 MPa
		Moment (kN · m)	22500	25600	
		Axial force (kN)	5710	4110	
	Reactor containment base	Shearing force (kN)	7270	8290	Reactor containment (dry well) Calculated value: 87 MPa Evaluation criteria: 278 MPa
		Moment (kN · m)	124000	153000	
		Axial force (kN)	3110	2350	
	Core shroud base	Shearing force (kN)	2590	3950	Core support structure (shroud support) Calculated value: 122 MPa Evaluation criteria: 300 MPa
		Moment (kN · m)	13800	21100	
		Axial force (kN)	760	579	
	Fuel subassembly	Relative displacement (mm)	16.5	33.2	Control rod (insertion performance) Evaluation criteria: 40.0 mm
Magnitude for assessment	Refueling floor	Magnitude (horizontal) (G)	0.97	1.21	Residual heat removal system pump (motor mounting bolt) Calculated value: 45 MPa Evaluation criteria: 185 MPa
		Magnitude (vertical) (G)	0.56	0.70	
	Base mat	Magnitude (horizontal) (G)	0.54	0.68	
		Magnitude (vertical) (G)	0.52	0.37	

<p>Floor response spectrum (reactor building)</p>	<p>< Intermediate floor (O.P. 18.70 m) ></p> 	<p>Main steam piping Calculated value: 208 MPa Evaluation standard value: 360 MPa</p> <p>Residual heat removal system pipe Calculated value: 87 MPa Evaluation standard value: 315 MPa</p>
<p>Floor response spectrum (reactor shield wall)</p>	<p>< Reactor shield wall base (O.P. 13.91 m) ></p> 	

“Report on the analysis of seismic records observed at the Onagawa Nuclear Power Station during the 2011 Tohoku District - off the Pacific Ocean Earthquake and the results of the tsunami survey (Outline)” dated April 7, 2011 and prepared by Tohoku Electric Power (Excerpt)

1. Seismic records observed at the Onagawa Nuclear Power Station

The Tohoku District – off the Pacific Ocean Earthquake was one of the largest earthquakes ever to hit Japan. Some of the maximum acceleration values observed on each floor of Unit 1, 2, and 3 reactor buildings exceeded the maximum response acceleration spectrum in terms of reference earthquake ground motion, S_s, which had been developed based on the revised version of the Regulatory Guide for Reviewing Seismic Design. However, there was little difference among the values (see Table 1).

Table 1. Comparison between the earthquake seismic records observed and the maximum response acceleration spectrum in terms of reference earthquake ground motion, S_s

Observation location		Seismic records observed			Maximum response acceleration spectrum in terms of reference earthquake motion, Ss (gal)		
		Maximum acceleration value (gal)					
		N-S direction	E-W direction	Vertical direction	N-S direction	E-W direction	Vertical direction
Unit 1	Rooftop	2000(*)	1636	1389	2202	2200	1388
	Refueling floor (5 th floor)	1303	998	1183	1281	1443	1061
	1 st floor	573	574	510	660	717	527
	Base mat	540	587	439	532	529	451
Unit 2	Rooftop	1755	1617	1093	3023	2634	1091
	Refueling floor (3 rd floor)	1270	830	743	1220	1110	968
	1 st floor	605	569	330	724	658	768
	Base mat	607	461	389	594	572	490
Unit 3	Rooftop	1868	1578	1004	2258	2342	1064
	Refueling floor (3 rd floor)	956	917	888	1201	1200	938
	1 st floor	657	692	547	792	872	777
	Base mat	573	458	321	512	497	476

(*) Information only, as the acceleration scaled out the seismometer

**“Summary of the analysis results of seismic records observed at the Onagawa Nuclear Power Station during The 2011 Tohoku District - off the Pacific Ocean Earthquake”
dated April 7, 2011 and prepared by Tohoku Electric Power (Excerpt)**

1. (Dispensed)

2. Seismic response analysis results using the observation records on the base mat

To roughly evaluate distortion in the seismic-resistant walls of the reactor buildings (the maximum response shearing strain) and the shearing force, which affected the seismic-resistant walls on each floor, a seismic response analysis was conducted using the seismic records observed on the base mat (Fig. 4).




Fig. 4. Outline of the seismic response analysis using the observation records on the base mat

(1) Confirmation of the maximum response shearing strain

The results of the seismic response analysis confirmed that the maximum response shearing strain was below the evaluation criteria* (Table 2).

Table 2. The maximum response shearing strain on the seismic-resistant walls of the reactor buildings


		Analysis results	Evaluation criteria*	(Ref.) Reference earthquake ground motion, S_s
Onagawa Unit 1	N-S direction	0.36×10^{-3}	2.0×10^{-3}	0.65×10^{-3}
	E-W direction	0.35×10^{-3}		0.56×10^{-3}
Onagawa Unit 2	N-S direction	0.49×10^{-3}		1.15×10^{-3}
	E-W direction	0.28×10^{-3}		0.55×10^{-3}
Onagawa Unit 3	N-S direction	0.81×10^{-3}		0.99×10^{-3}
	E-W direction	0.18×10^{-3}		0.41×10^{-3}

* The evaluation criteria is specified in the “Rules of Seismic Design Technology for Nuclear Power Stations (JEAC4601-2008)” by the Japan Electric Association. They are obtained by multiplying the safety factor of 2 on the final shearing strain of the ferroconcrete seismic-resistant walls.

(2) Confirmation of shearing forces affecting seismic-resistant walls on each floor

The results of the seismic response analysis confirmed that the shearing force, which had affected the seismic-resistant walls on each floor, was below the shearing force (elastic limit strength) that the reinforcement elastic range on each floor could bear (Fig. 5).

Fig. 5. Confirmation of shearing force affecting seismic-resistant walls on each floor of the reactor buildings



Conclusion and future efforts

As a result of the analysis of the earthquake observation records obtained from the Onagawa Nuclear Power Station, some values exceeded reference earthquake ground motion, Ss. However, there was little difference among them. In addition, through the seismic response analysis using the observation records, it was confirmed that the functions of the reactor buildings were maintained during the earthquake as well.

“Report on the analysis and evaluation of earthquake seismic records observed at the Onagawa Nuclear Power Station during the 2011 Tohoku District - off the Pacific Ocean Earthquake and the assessment of the impacts on the equipment important for seismic safety (Outline)” dated July 28, 2011 and prepared by Tohoku Electric Power (Excerpt)

1. Impact assessment of equipment important for seismic safety

Rough evaluations (evaluation of structural strengths and evaluation of the maintenance of dynamic functions) of the functions of the main equipment at the time of earthquakes, which “shut down” and “cool” the reactors and “confine” radioactive substances at the Onagawa Nuclear Power Station Units 1, 2, and 3 and are important for seismic safety, were conducted on the impacts of the Tohoku District – off the Pacific Ocean Earthquake on March 11, 2011 (the “March 11 Earthquake”) and the Off-Miyagi Prefecture Earthquake on April 7, 2011 (the “April 7 Earthquake”) based on the results of an analysis of the reactor buildings (reported on April 7 and 25, 2011, respectively) using the seismic records observed from each earthquake.

The results confirmed that the values generated by each piece of equipment during the March 11 Earthquake and the April 7 Earthquake were below the evaluation criteria for maintaining its functions (see Table 1 and Table 2).

Table 1. Structural strength evaluation results

Function	Equipment evaluated (areas covered)		Generated value (N/mm ²)		Evaluation standard value (N/mm ²)	Judgment
			March 11 Earthquake	April 7 Earthquake		
Shutdown	Core support structure (shroud support leg)	Unit 1	71	69	250	○
		Unit 2	85	111	209	○
		Unit 3	80	58	209	○
Cooling	Residual heat removal system pump (mounting bolt)	Unit 1	88	103	185	○
		Unit 2	22	21	444	○
		Unit 3	27	26	444	○
	Residual heat removal system pipe (pipe body)	Unit 1	140	151	363	○
		Unit 2	114	157	366	○
		Unit 3	204	213	324	○
Confinement	Reactor pressure vessel (foundation bolt)	Unit 1	62	71	222	○
		Unit 2	117	89	499	○
		Unit 3	72	73	499	○
	Reactor containment (sand cushion)	Unit 1	120	129	255	○
		Unit 2	0.34	0.41	1	○
		Unit 3	0.33	0.31	1	○
	Main steam piping (pipe body)	Unit 1	135	139	366	○
		Unit 2	157	207	375	○
		Unit 3	240	304	375	○

Table 2. Results of an evaluation of the maintenance of dynamic functions

Function	Equipment evaluated (areas covered)		Relative displacement (mm)		Evaluation standard value (mm)	Notes
			March 11 Earthquake	April 7 Earthquake		
Shutdown	Control rod (insertion performance) (relative displacement of fuel subassembly)	Unit 1	20.5	17.5	40.0	<ul style="list-style-type: none"> • At the time of the March 11 Earthquake: already confirmed that all control rods were inserted. • At the time of the April 7 Earthquake: already confirmed that all control rods were inserted.
		Unit 2	13.9	10.2	40.0	
		Unit 3	12.2	9.5	40.0	

Existing and newly introduced accident management measures (Unit 1)

Function	Newly introduced accident management measures (Developed from March, 1994)	Existing accident management measures (as of March, 1994)
Reactor shutdown	X Alternative reactivity control (RPT and ARI)	X Manual scram X Manual operation of the water level controls and the standby liquid control system
Water injection into reactor and containment	X Alternative water injection measures (measures to inject water into the reactor and containment by the make-up water condensate and the fire protection system pump; and measures to inject water into the reactor by the shutdown cooling system from the containment cooling system)	X Manual startup of ECCS etc. X Manual depressurization of the reactor and operation of low pressure water injection X Alternative water injection measures (measures to inject water into the reactor by condensate and the feed water system and control rod drive hydraulic system)
Heat injection from containment	X Cooling container function <ul style="list-style-type: none"> * Alternative cooling using the drywell cooler and reactor water clean-up system * Restoration of the broken equipment of the containment cooling system * Pressure-resistant vent 	X Cooling container function <ul style="list-style-type: none"> * Manual startup of the containment cooling system * Vent passing through the atmospheric control system and standby gas treatment system
Power supply system	X Power supply measures <ul style="list-style-type: none"> * Accommodation of power supply (480V of accommodation from an adjacent plant) * Restoration of the broken equipment of the emerging diesel generator * Dedicated use of the emerging diesel generator 	X Power supply measures <ul style="list-style-type: none"> * Restoration of off-site power and manual startup of the emerging diesel generator * Interconnectivity of power supply (6.9kV of interconnectivity from an adjacent unit)

Compiled from the "Report on Development of Accident Management for Fukushima Dai-ichi NPS" (May, 2002) by

Existing and newly introduced accident management measures (Units 2 to 5)

Function	Newly introduced accident management measures (Developed from March, 1994)	Existing accident management measures (as of March, 1994)
Reactor shutdown	X Alternative reactivity control (RPT and ARI)	X Manual scram X Manual operation of the water level controls and the standby liquid control system
Water injection into reactor and containment	X Alternative water injection measures (measures to inject water into the reactor container by make-up water condensate and the fire protection system pump) X Automated depressurization of the reactor	X Manual startup of ECCS etc. X Manual depressurization of the reactor and operation of low pressure water injection X Alternative water injection measures (measures to inject water into the reactor by condensate and the feed water system and control rod drive hydraulic system†)
Heat injection from containment	X Cooling container function * Alternative cooling using the drywell cooler and reactor water clean-up system * Restoration of the broken equipment of the residual heat removal system * Pressure-resistant vent	X Cooling container function * Manual startup of the containment cooling system * Vent passing through the atmospheric control system and standby gas treatment system
Power supply system	X Power supply measures * Accommodation of power supply (480V of accommodation from an adjacent plant) * Restoration of the broken equipment of the emerging diesel generator * Dedicated use of the emerging diesel generator	X Power supply measures * Restoration of off-site power and manual startup of the emerging diesel generator * Interconnectivity of power supply (6.9kV of interconnectivity from an adjacent unit)


†: Not implemented at Unit 2

Compiled from the “Report on Development of Accident Management for Fukushima Dai-ichi NPS” (May, 2002) by TEPCO

Existing and newly introduced accident management measures (Unit 6)


Function	Newly introduced accident management measures (Developed from March, 1994)	Existing accident management measures (as of March, 1994)
Reactor shutdown	X Alternative reactivity control (RPT and ARI)	X Manual scram X Manual operation of the water level controls and the standby liquid control system
Water injection into reactor and containment	X Alternative water injection measures (measures to inject water into the reactor container by make-up water condensate and the fire protection system pump) X Automated depressurization of the reactor	X Manual startup of ECCS etc. X Manual depressurization of the reactor and operation of low pressure water injection X Alternative water injection measures (measures to inject water into the reactor by the feed water system and control rod drive hydraulic system; measures to inject water into the reactor container by a seawater pump)
Heat injection from containment	X Cooling container function * Alternative cooling using the drywell cooler and reactor water clean-up system * Restoration of the broken equipment of the residual heat removal system * Pressure-resistant vent	X Cooling container function * Manual startup of the containment spray cooling system * Vent passing through the atmospheric control system and standby gas treatment system
Power supply system	X Power supply measures * Accommodation of power supply (480V of accommodation from an adjacent plant and 6.9kV of accommodation from the dedicated diesel generator for the high pressure core spray system) * Restoration of the broken equipment of the emerging diesel generator * Dedicated use of the emerging diesel generator	X Power supply measures * Restoration of off-site power and manual startup of the emerging diesel generator * Interconnectivity of power supply (6.9kV of interconnectivity from an adjacent unit)

Compiled from the “Report on Development of Accident Management for Fukushima Dai-ichi NPS” (May, 2002) by TEPCO




Conceptual diagram of alternative water injection facilities (Unit 1)


Compiled from the "Report on Development of Accident Management for Fukushima Dai-ichi NPS" (May, 2002) by TEPCO



Conceptual diagram of alternative water injection facilities (Units 2 to 5)




Conceptual diagram of alternative water injection facilities (Unit 6)



Attachment VI-7

Conceptual diagram of hardened vent system (Units 1 to 6)



Route (A) : Capable of an AC power supply of 6.9kV.

Line for supplying high voltage AC power used until March 1994


Route (B) : Capable of an AC power supply of 480V.

Tie line for supplying low voltage AC power installed from June 1998 to August 2000

Conceptual diagram of the power supply interconnectivity (Units 1 to 6)

Compiled from the "Report on Development of Accident Management for Fukushima Dai-ichi NPS" (May, 2002) by TEPCO

Plot plan of the Fukushima Dai-ichi NPS



Explanatory note

- R/B Reactor building
- T/B Turbine building
- RW/B Reactor waste treatment building
- C/B Control building
- S/B Service building
- Common auxiliary facilities (shared pool)
- Ultrahigh voltage switchyard
- Main office building
- Seismic isolation building

Attachment VI-9

福島第一原子力発電所 配置図：General layout of the Fukushima Daiichi NPS

図上部 左⇒右

- ① 双葉町側：Futaba-machi
- ② 大熊町側：Okuma-machi
- ③ 取水路開渠：Intake channel open ditch
- ④ カーテンウォール：Curtain wall
- ⑤ 取水口：Water intake
- ⑥ 東波防堤：East breakwater
- ⑦ カーテンウォール：Curtain wall
- ⑧ 取水路開渠：Intake channel open ditch

図中央部 左⇒右

- ⑨ 超高压開閉所：Ultra high voltage switch yard
- ⑩ 66KV開閉所：66 kV switching station
- ⑪ 第1土捨場：Spoil bank No.1
- ⑫ 固体廃棄物貯蔵所：Solid waste storage
- ⑬ 計測器予備品倉庫：Storage for spare measurement equipment
- ⑭ 定検用機材倉庫：Storage for equipment used for periodic inspections
- ⑮ 物揚場：Shallow draft quay
- ⑯ 使用済燃料輸送容器保管建屋：Building for storing spent fuel transport
- ⑰ 駐車場：Parking lot
- ⑱ 駐車場：Parking lot
- ⑲ 事務本館：Administration building
- ⑳ 免震重要棟：Seismic isolation building
- ㉑ 駐車場：Parking lot
- ㉒ 超高压開閉所：Ultra high voltage switchyard
- ㉓ 超高压開閉所：Ultra high voltage switchyard
- ㉔ 運用補助共用施設(共用プール)：Auxiliary common facilities (common pool)
- ㉕ 放射性廃棄物集中処理施設：Centralized radioactive waste disposal facility
- ㉖ 放射性廃棄物集中処理施設：Central radioactive waste disposal facility
- ㉗ 排風気建屋：Exhaust building
- ㉘ 焼工建屋：Incinerator and machine building
- ㉙ 高放射性固体廃棄物処理建屋：High-radioactive solid waste disposal building
- ㉚ 高温焼却建屋：High temperature incinerator building

⑪ 共用サプレッションプールサージタンク建屋 : Common suppression pool surge tank building

⑫ 予備変電所 : Auxiliary substation

⑬ 用水池 : Reservoir

図下部 左⇒右

⑭ 双葉線 1 号・2 号 : Futaba Transmission Line, L1 and L2

⑮ 夜ノ森線 1 号・2 号 : Yorunomori Transmission Line, L1 and L2

⑯ ろ過水タンク : Filtered water tank

⑰ 多目的運動場 : Sports ground

⑱ 登録センター : Registry center

⑲ 駐車場 : Parking lot

⑳ 大熊線 1 号・2 号 : Okuma Transmission Line, L1 and L2

㉑ 大熊線 3 号・4 号 : Okuma Transmission Line, L3 and L4


㉒ 福島原子力技能訓練センター : Fukushima Nuclear Skills Training Center

㉓ 駐車場 : Parking lot

㉔ 請負企業センター : Contractor Center

㉕ サービスホール : Service hall

Plant layout for Units 1 to 4 of the Fukushima Dai-ichi NPS



Based on data and documents by
Tokyo Electric Power Company


Attachment VI-10: Plant layout for Units 1 to 4 of the Fukushima Dai-ichi NPS

- ①物揚場：Shallow Draft Quay
- ②純水ポンプ建屋：Deionized water pump building
- ③No.1 純水タンク：Deionized water tank 1
- ④No.2 純水タンク：Deionized water tank 2
- ⑤保健安全センター別館：Health and Safety Center annex
- ⑥薬品貯槽：Chemical storage
- ⑦厚生棟：Welfare building
- ⑧（旧）水処理建屋：(Old) Water disposal building
- ⑨事務本館別館：Administration annex
- ⑩総合情報等：General information building
- ⑪飲料水タンク：Drinking water tank
- ⑫重油タンク：Heavy oil tank
- ⑬No.1 危険物倉庫：Hazardous materials storage 1
- ⑭消火栓装置：Foam fire extinguishing system
- ⑮予備品倉庫：Storage for spare items
- ⑯新サービス建屋：New service building for Units 1 and 2
- ⑰1 号機復水貯蔵タンク:Condensate storage tank for Unit 1
- ⑱逆洗弁ピット：Reversing valve pit
- ⑲1 号機タービン建屋：Turbine building for Unit 1
- ⑳起動変圧器：Startup transformer
- ㉑主変圧器：Main transformer
- ㉒地震観測小屋:Cabin for seismic observation
- ㉓窒素供給装置:Nitrogen supply equipment
- ㉔1, 2 号機取水設備電源室:Power room for the water intake facility for Units 1 and 2
- ㉕機械室:Machinery room
- ㉖No. 1 軽油タンク:Light oil tank 1
- ㉗浄化槽:Water-purifier tank
- ㉘2 号機復水貯蔵タンク：Condensate storage tank for Unit 2
- ㉙1, 2 号機サービス建屋:Service building for Units 1 and 2
- ㉚1, 2 号機サービスエリア：Service area for Units 1 and 2
- ㉛1 号機コントロール建屋：Control building for Unit 1
- ㉜2 号機コントロール建屋：Control building for Unit 2
- ㉝1 号機廃棄物処理建屋：Radioactive waste disposal building for Unit 1
- ㉞2 号機廃棄物処理建屋：Radioactive waste disposal building for Unit 2

- ㊿1, 2 号機排気筒 : Exhaust stack for Units 1 and 2
- ㊿1, 2 号機排気筒モニタ収納小屋 : Cabin for monitoring the exhaust stack for Units 1 and 2
- ㊿1, 2 号機超高压開閉所 Ultra-high voltage switchyard for Units 1 and 2
- ㊿1～4 号機共用所内ボイラ直流電源室 : DC power room for the common house boiler for Units 1 to 4
- ㊿所内変圧器 : Unit auxiliary transformer
- ㊿No.2 危険物倉庫 : Hazardous materials storage 2
- ㊿1～4 号機発電機注入用窒素ガスボンベ室 : Nitrogen gas cylinder room for injection into the generator of Units 1 to 4
- ㊿No.2 軽油タンク Light oil tank 2
- ㊿3 号機復水貯蔵タンク : Condensate storage tank for Unit 3
- ㊿立坑 : Pit
- ㊿メタクラ 2 S A 建屋 : Metal-clad switchgear 2SA building
- ㊿3 号機原子炉建屋 : Reactor building for Unit 3
- ㊿1, 2 号機活性炭ホールドアップ装置建屋 : Building for activated carbon hold up equipment for Units 1 and 2
- ㊿3 号機活性炭ホールドアップ装置建屋 : Building for activated carbon hold up equipment for Unit 3
- ㊿4 号機スクリーン電源室 : Power room for the Unit 4 screen
- ㊿北側立坑 : North pit
- ㊿3 号機主発電機励磁装置盤建屋 : Building for energizing the control panel of the main generator of Unit 3
- ㊿励磁電源変圧器 : Exciter transformer
- ㊿汚損検出器 : Pollution detector
- ㊿計算機室冷凍機 : Cooling machine for the computer room
- ㊿タービン建屋換気系排気筒 : Turbine building ventilation system exhaust stack
- ㊿排風気建屋 : Exhaust building
- ㊿可燃性雑固体廃棄物焼却設備及び工作機械室 (焼工建屋) : Incinerator for burnable solid waste and the machine tool room (incinerator and machine building)
- ㊿放射性廃棄物集中処理施設 (プロセス補助建屋) : Central radioactive waste disposal facility (building for auxiliary processes)
- ㊿放射性廃棄物集中処理施設 (プロセス主建屋) : Central radioactive waste disposal facility (building for main processes)
- ㊿高放射線性固体廃棄物処理建屋 (サイトバンカー) : Highly radioactive solid waste disposal building (on-site bunker)
- ㊿高温焼却建屋 : High temperature incinerator building

- ⑥② 共用サプレッションプールサージタンク建屋 : Common suppression pool surge tank building
(common pool)
- ⑥③ 軽油移送ポンプ : Light oil transfer pump
- ⑥④ 水素トレーラー : Hydrogen trailer
- ⑥⑤ 液体酸素タンク : Storage for liquid oxygen

Plant layout for Units 5 and 6 of the Fukushima Dai-ichi NPS



Based on data and documents by
Tokyo Electric Power Company

Attachment VI-10: Plant layout for Units 5 and 6 of the Fukushima Dai-ichi NPS

- ①循環水ポンプ: Water circulating pump
- ②5/6 号機サンプリング建屋: Sampling building for Units 5 and 6
- ③6 号機ディーゼル発電機建屋: Diesel generator building for Unit 6
- ④6 号機 MG セット建屋: Building for the MG set of Unit 6
- ⑤6 号機タービン建屋: Turbine building for Unit 6
- ⑥電気品室: Electrical items room
- ⑦非常用ディーゼル発電機室: Emergency diesel generator room
- ⑧長期地震観測建屋: Building for long-term seismic observation
- ⑨廃棄物処理エリア: Radioactive waste disposal area
- ⑩連絡通路: Passageway
- ⑪開閉所: Switchyard
- ⑫6 号機超高圧開閉所: Ultra-high voltage switchyard for Unit 6
- ⑬5/6 号機廃棄物地下貯蔵設備建屋: Underground storage for radioactive waste for Units 5 and 6
- ⑭6 号機雑固体処理建屋: Building for the disposal of solid waste for Unit 6
- ⑮6 号機所内変圧器: Unit auxiliary transformer for Unit 6
- ⑯5 号機起動変圧器: Startup transformer for Unit 5
- ⑰サプレッションプール水タンク: Suppression pool water tank
- ⑱No.4 資材倉庫: Material storage 4
- ⑲励磁変圧器: Exciter transformer
- ⑳窒素供給装置: Nitrogen supply equipment
- ㉑水素供給設備制御室: Control room for hydrogen supply equipment
- ㉒5 号所内ボイラー建屋: Building for the Unit 5 house boiler
- ㉓主排気ダクト: Main exhaust duct
- ㉔6 号機復水貯蔵タンク: Condensate storage tank for Unit 6
- ㉕純水タンク: Deionized water tank 1

	Before core damage Accident management to prevent core damage	After core damage Accident management to mitigate the impact when core damage has occurred	Procedure manual for accident management with or without core damage
For operators	<div>Operating procedures in the event of an accident (symptom-based) EOP</div> <p>*Procedure manual containing procedures for observed symptoms of the plant, regardless of what event causes the accident *Contains response procedures to prevent core damage as part of accident management</p>	<div>Operating procedures in the event of an accidents (severe accidents) SOP</div> <p>*Contains response procedures to mitigate the impact after core damage as part of accident management</p>	<div>Operating procedures in the event of an accident (event-based) AOP</div> <p>*Procedure manual containing procedures according to the scenario of each expected design event *Contains the operation of power supply interconnectivity as part of accident management</p>
For the support organization		<div>Accident management guidelines AMG</div> <p>Contains procedures, criteria for decision-making, information on technical data etc. and impact forecasts as guidelines for comprehensively judging measures for impact mitigation after core damage.</p>	<div>Guidelines for restoration procedures (RHR and D/G)</div> <p>Contains guidelines for restoring the residual heat removal system (the containment cooling system for Unit 1) and the emergency diesel generator system, which are particularly important for security, in the event of a breakdown.</p>

*AOP: Abnormal operating procedures

*SOP: Severe accident operating procedures

*EOP: Emergency operating procedures

*AMG: Accident management guidelines

Overview of the configuration of accident management procedures

Compiled from the "Report on Development of Accident Management for Fukushima Dai-ichi NPS" (May, 2002)

Attachment VI-12

Method and frequency of accident management training programs

Training target		Content of training	Training method/frequency	
Support organization personnel	Personnel other than engineering team	Primary knowledge	Training method	Self-study Lectures by the Technical GM, etc.
			Frequency	Once while in the job
	The site superintendent, deputy site superintendent of the headquarters, and section chief, assistant section chief, and members of the engineering team	Primary knowledge	Training method	Self-study Lectures by the Technical GM, etc.
		Advanced knowledge	Frequency	Once while in the job
Operators	Shift supervisors and assistant shift supervisors	Primary knowledge	Training method	Self-study Lectures by the Electricity Generation GM, etc.
		Advanced knowledge	Frequency	Once while in the job
	Everyone under the senior operator	Primary knowledge	Training method	Self-study Lectures by the Electricity Generation GM, etc.
			Frequency	Once while in the job

NB: The operators in corresponding operations for accident management to fullest possible the extent are trained by the Full Scope Simulator at the BWR Operator Training Center.

Content of accident management training (an example)

Target	Content
Personnel of the support organization and all shift operators	Primary knowledge Overview of AM (what "AM" means) Overview of severe accidents (what "severe accident" means) Representative features of accident scenarios and their development An overview of the types of equipment for each function Positioning of accident management guidelines (AMG) etc.
Support organization: Site superintendent Deputy site superintendent Section chief of engineering teams Assistant section chief Members of engineering teams	Primary knowledge Overview of AM (what "AM" means) Overview of severe accidents (what "severe accident" means) Representative features of accident scenarios and their development An overview of the types of equipment for each function Positioning of accident management guidelines (AMG) etc.
Operators : Shift Supervisor Assistant Shift Supervisor	Advanced knowledge AMG etc. (flow guide) Development of representative accident scenarios and events at the plant Priorities corresponding to the plant's equipment for each function Overview of unknown events (metal-water reactions, etc.) Situation of the unknown event, method of confirmation and corresponding operations of unknown phenomena

NB: The training methods, frequency and content are due to revision, as appropriate.

Compiled from the "Report on Development of Accident Management for Fukushima Dai-ichi NPS" (May, 2002) by TEPCO

Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company: timeline of activities (2011)

Month	Day	Main Activities
May	24	The government decides to establish the Investigation Committee at a Cabinet meeting. The Prime Minister appoints Dr. Yotaro Hatamura as chairperson.
May	27	The Prime Minister appoints Dr. Kazuo Oike, Dr. Shizuko Kakinuma, Mr. Yukio Takasu, Mr. Toshio Takano, Mr. Yasuro Tanaka, Ms. Yoko Hayashi, Mr. Michio Furukawa, Mr. Kunio Yanagida and Mr. Hitoshi Yoshioka as committee members.
Jun.	7	First Session Address by the Prime Minister. Address by the Chairperson. The Committee determines management procedures and investigation items. The Chairperson appoints Mr. Seiji Abe and Dr. Masao Fuchigami as technical advisors. Hearing of explanations from the Nuclear and Industrial Safety Agency of the Ministry of Economy, Trade and Industry.
Jun.	17	Inspection of Tokyo Electric Power Company's Fukushima Daiichi and Daini Nuclear Power Stations.
Jun.	30	As above.
Jul.	8	Second Session The Committee arranges the handling of materials and information, relevant interview methods and other procedures. The Committee determines investigation and verification items (details). Hearing of explanations from Tokyo Electric Power Company.
Jul.	15	Inspection of the Tokai Daini Nuclear Power Station of the Japan Atomic Power Company, Ltd.
Jul.	24	The Chairperson has a meeting with Mr. John P. Holdren, Assistant to the US President for Science and Technology.
Jul.	27	The Chairperson has a meeting with Mr. Yukiya Amano, Director General of the International Atomic Energy Agency (IAEA).
Aug.	5	Inspection of the Onagawa Nuclear Power Station of the Tohoku Electric Power Company, Inc.
Aug.	19	Inspection of the Haramachi Thermal Power Plant of the Tohoku Electric Power Company, Inc.
Sep.	9	Inspection of the Hamaoka Nuclear Power Station of the Chubu Electric Power Company, Inc.
Sep.	27	Third Session Reports on the investigation status.
Oct.	14	Inspection of the Kashiwazaki Kariwa Nuclear Power Station of Tokyo Electric Power Company.
Oct.	28	Fourth Session Reports on the investigation status. Discussion for the Interim Report.
Nov.	9	Hearing of opinions of Toshitsuna Watanabe, Mayor of Okuma, and Katsutaka Idogawa, Mayor of Futaba.
Nov.	29	Fifth Session Discussion of the Interim Report plan.
Dec.	26	Sixth Session Summary and announcement of the Interim Report.

Establishment of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company

May 24, 2011
Cabinet Decision

1. Purpose

The government establishes the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company (hereinafter referred to as the “Investigation Committee”) with the aim of making policy proposals on measures to prevent further spread of the damage caused by the accident and a recurrence of similar accidents in the future. This will be done by conducting a multifaceted investigation in an open and neutral manner that is accountable to the Japanese public to determine the causes of the accident at the Fukushima Daiichi and Daini Nuclear Power Stations and the causes of the damage due to the accident.

2. Composition of the Investigation Committee

- (1) The members of the Investigation Committee shall be appointed by the Prime Minister from persons with academic and other various backgrounds.
- (2) The Prime Minister shall appoint the chairperson of the Investigation Committee from among its members.
- (3) The chairperson may appoint technical advisors to give the Investigative Committee advice on technical matters.
- (4) The Investigation Committee may, when necessary, ask any relevant minister including the Prime Minister, official of any relevant administrative organizations, officer or employee of relevant businesses, official of any international organization on nuclear energy, or any other relevant person, to attend a meeting with the Investigation Committee.

3. Responsibilities of the relevant ministers

- (1) All relevant ministers and officials of related administrative organizations shall fully cooperate with the operations of the Investigation Committee and shall not refuse requests from the Investigation Committee for materials and explanations without reasonable grounds.
- (2) The ministers concerned shall exercise their authority based on applicable laws to instruct the relevant businesses to fulfill any requests by the Investigation Committee’s for on-site investigations, materials and explanations.

4. Other matters

Administrative affairs pertaining to the Investigation Committee shall be conducted by the Cabinet Secretariat in cooperation with the relevant administrative organizations.

Rules on the establishment of the Secretariat of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company

May 31, 2011

Decision of the Prime Minister

ESTABLISHMENT AND DUTIES

Article 1. The Secretariat of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company (hereinafter referred to as the “Secretariat”) shall be established in the Cabinet Secretariat with the aim of assisting the investigation by the “Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company” and dealing with the administrative work of the Committee.

STRUCTURE

Article 2. The Secretariat shall have a secretary-general, counselor, senior planning officer and other necessary officials.

(2) The secretary-general shall manage the administrative work of the Secretariat.

(3) The counselor shall participate in the investigation, planning and development of important matters by following the instructions of the secretary-general.

(4) The senior planning officer shall be engaged in the administrative work related to the investigation, planning and development of technicalities by following the instructions of the secretary-general.

(5) The secretary-general, counselor, senior planning officer and other officials may be employed part-time.

POLICY AND TECHNICAL INVESTIGATION ADVISORS

Article 3. The Secretariat may have policy and technical investigation advisors.

(2) The policy and technical investigation advisors shall investigate and state their opinions on technical matters related to the jurisdiction of the Secretariat and handle the administrative work otherwise ordered by following the instructions of the secretary-general.

(3) The policy and technical investigation advisors may be employed part-time.


SUPPLEMENTARY RULE

Article 4. In addition to what is provided for in the preceding Articles, necessary matters in relation to the internal organization of the Secretariat shall be specified by the secretary-general.

SUPPLEMENTARY PROVISION

The rules herein shall be effective from June 1, 2011.

Structure of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company



List of experts (policy and technical investigation advisors) at the Secretariat of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company

Social System Investigation Team

【Team Director】

Dr. Hideyuki Horii

Professor, Department of Civil Engineering, Graduate School of Engineering, The University of Tokyo

(Area of specialization: sociotechnology, safety and security)

【Team Member】

Mr. Hideaki Shiroyama

Professor, Graduate School for Law and Politics, The University of Tokyo

(Area of specialization: public administration)

Accident Causes Investigation Team

【Team Director】

Dr. Seiichi Koshizuka

Professor, Department of Systems Innovation, Graduate School of Engineering, The University of Tokyo

(Area of specialization: computer simulation, severe accident analysis for nuclear reactors)

【Team Member】

Dr. Hiroyuki Oigawa

Director, Research Coordination and Promotion Office, Nuclear Science and Engineering Directorate, Japan Atomic Energy Agency

(Area of specialization: reactor physics)

【Team Member】

Dr. Yuji Nakasone

Professor, Department of Mechanical Engineering, Faculty of Engineering, Tokyo University of Science

(Area of specialization: strength of materials, computational solid mechanics)

Damage Expansion Prevention Measures Investigation Team

【Team Director】

Dr. Toshitaka Katada

Professor, Director, Research Center for Disaster Prevention in the Extended Tokyo Metropolitan Area, Gunma University

(Area of specialization: disaster information, evacuation behavior, disaster education)

【Team Member】

Dr. Katsuya Yamori

Professor, Disaster Prevention Research Institute, Kyoto University

(Area of specialization: disaster psychology, social psychology)

【Team Member】

Mr. Naoya Sekiya

Associate Professor, Department of Media and Communications, Faculty of Sociology, Toyo University

(Area of specialization: social psychology, disaster information theory)

**Management procedures of the Investigation Committee on the Accident
at the Fukushima Nuclear Power Stations of Tokyo Electric
Power Company**

June 27, 2011

Decision of the Investigation Committee on the Accident at the Fukushima Nuclear Power
Stations of Tokyo Electric Power Company

In addition to what is provided for in “Establishment of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company (Cabinet Decision on May 24, 2011),” the procedures of meetings and other matters concerning the administration of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power (hereinafter referred to as the “Investigation Committee”) shall be determined as follows:

DEPUTY CHAIRPERSON

Article 1. In the absence of the Chairperson, a Committee member nominated in advance by the Chairperson shall act on their behalf.

PROCEEDINGS OF THE INVESTIGATION COMMITTEE

Article 2. The Investigation Committee shall convene when summoned by the Chairperson.

- (2) The Investigation Committee may not hold a meeting unless the majority of its members are present.
- (3) In principle, decisions by the Investigation Committee shall be made with the unanimous agreement of all attendees. However, in the event that unanimous agreement is not reached, decisions shall be made by the majority of the members present at the discretion of the Chairperson.

DISCLOSURE OF PROCEEDINGS OF THE INVESTIGATION COMMITTEE

Article 3. In principle, proceedings of the Investigation Committee shall be

disclosed. However, they may not be disclosed in the event their disclosure is likely to be detrimental to the rights or interests of any third party or the public's interest, or otherwise approved by the Chairperson.

- (2) In principle, documents distributed at and proceedings of a meeting of the Investigation Committee shall be disclosed. However, they may not be disclosed in the event their disclosure is likely to be detrimental to the rights or interests of any third party or the public's interest, or otherwise approved by the Chairperson.

SUBCOMMITTEE

Article 4. The Investigation Committee may resolve to have

subcommittees if they are necessary for studying and deliberating specialized matters.

- (2) In addition to what is specified by the resolution described in the preceding paragraph, necessary matters for the administration of subcommittees shall be specified by the Chairperson.

PARTICIPATION OF TECHNICAL ADVISORS IN THE INVESTIGATION COMMITTEE

Article 5. Technical Advisors may attend the Investigation Committee meetings with the approval of the Chairperson to state their opinions on matters requested by the Chairperson.

INSTRUCTION FOR THE SECRETARIAT TO INVESTIGATE

Article 6. The Investigation Committee and the Chairperson may have the Secretariat conduct necessary investigations.

MISCELLANEOUS PROVISION

Article 7. In addition to what is provided for

in the preceding Articles, necessary matters for the administration of the Investigation Committee shall be specified by the Chairperson.

Information and informative materials to be handled without disclosure

July 8, 2011

Terms of the Investigation Committee on the Accident at the Fukushima Nuclear Power
Stations of Tokyo Electric Power Company

1. (1) The members and technical advisors (hereinafter referred to as “Members and Advisors”) of the Investigation Committee on the Accident at the Fukushima Nuclear Power Stations of Tokyo Electric Power Company (hereinafter referred to as the “Committee”) shall not disclose confidential information that becomes known to them during the investigation process of the Committee even after the completion of their roles as Members and Advisors.

(2) Information and informative materials obtained during the investigation process shall be kept securely in an appropriate place, such as the Secretariat of the Committee.

2. (1) In the event that the Committee is provided with information or informative materials from other parties on the condition that the information or informative materials are handled confidentially, it shall state specific reasons for their nondisclosure, including the possibility that the disclosure of such information or informative materials is not likely to be in the public’s interest or may be detrimental to the rights and interests of any party concerned (including parties other than the information provider. This applies hereinafter). The Committee shall handle such information and informative materials confidentially if the Committee finds reasonable grounds for nondisclosure.

(2) If the Committee finds reasonable grounds (e.g., the potential for the interest of the public or the rights and interests of the parties concerned to be compromised) for the nondisclosure of information or informative materials not falling under (1), the Committee shall handle the information or informative materials confidentially.

(3) With regard to (1) and (2), in times of urgency, the Chairperson of the Committee may use his discretion to determine whether the Committee should handle the

information or informative materials confidentially.

(4) When preparing the interim and final reports, the Committee shall treat such information and informative materials confidentially.

3. If other parties handle information or informative materials confidentially and do not comply with the Committee's request for their provision despite the Committee not finding any reasonable grounds for nondisclosure, the Committee shall take appropriate measures, such as disclosing to the public the response of the parties.

Methods of Interview

July 8, 2011

Terms of the Investigation Committee on the Accident at the Fukushima Nuclear Power
Stations of Tokyo Electric Power Company

1. Interviewer

In many cases, Secretariat members take the initiative in holding interviews as part of their fact-finding missions. Secretariat members, however, shall hold them together with the Committee members or technical advisors (hereinafter referred to as “Members and Advisors”) should they wish to participate.

NOTE: The Secretariat shall inform Members and Advisors of the details of an interview in advance, and those wishing to participate shall do so. However, some changes may be required depending on the number of Members and Advisors wishing to participate.

2. Method of Interviewing

(1) Interviews, in principle, shall be conducted in confidence and in small groups.

NOTE 1: Depending on respective interviewees, there are various reasons for the above, including the following, which are considered major reasons: 1.) To obtain a testimony of truth; 2.) In many cases, interviews deal with information which is inappropriate to publicly disclose (e.g. for reasons pertaining to public security); 3.) Interviews often deal with testimonies relating to personal privacy.

(2) With the exception of interviews concerning information specified in 2.) of NOTE 1, an interview shall be disclosed in an appropriate manner (e.g., disclosure to the media or by recording) with the consent of the interviewee.

NOTE 2: The reasons specified in NOTE 1 are to keep interviews confidential. However, if the interviewee agrees to the interview being made available to the public, it shall be conducted in an open manner or on the premise that it will be disclosed. This is because in such cases, the reasons specified in 1.) and 3.) of NOTE 1 will not pose a problem while the issue stated in 2.) will be resolved by

the exception stated in (2) of 2. (“with the exception of interviews concerning information specified in 2.) of NOTE 1”).

3. Recording of Interviews

When an interview that is not to be disclosed is held, the Secretariat member in charge shall compile the information delivered in the interview and create a transcript.

In addition, the interview shall be recorded with the consent of the interviewee on a digital voice recorder to ensure accuracy. If the interviewee does not agree or there is no time to arrange a digital voice recorder, the interview shall be held without being recorded, in which case, however, the Secretariat member in charge shall take notes as accurately as possible.

4. Handling of Interview Results

- (1) The Secretariat shall inform the Members and Advisors of the completion of each interview without delay.
- (2) The Secretariat shall inform the Members and Advisors of the content of interviews as necessary when it compiles and reports the investigation results to the Committee.
- (3) If the Members and Advisors ask to read the testimonies, in principle, the Secretary shall directly deliver copies of the testimonies to them by hand (or by an appropriate alternative method in order to prevent the information being leaked). If the Members and Advisors request the recordings of the testimonies, they shall listen to them at the Secretariat office.

5. Use of Interview Results

- (1) Interview results shall not be used to pursue liability.

The Committee is not established for the purpose of pursuing the liability of any party. Therefore, the Committee shall not use material (i.e., the content of testimonies) obtained from interviews for the purpose of pursuing the liability of

any party.

(2) When the Secretariat compiles the investigation results of interviews that are not to be disclosed about each individual's involvement in contributing to the causes of the accident and spread of damage, the Secretariat shall give due consideration so that no individual cooperating with the investigation shall be identified.

Although the Secretariat shall disclose as necessary transcripts obtained from interviews not to be disclosed, it shall not divulge any information that may identify the interviewee or which the interviewee requests not to be disclosed. As a recording is likely to identify the interviewee, no recording shall be disclosed as long as the interviewee requests its nondisclosure.

List of English Abbreviations

Abbreviation	English Term
ADS	Automatic Depressurization System
AEC	Atomic Energy Commission
AM	Accident Management
AMG	Accident Management Guideline
AOP	Abnormal Operating Procedures
AO弁	Air Operated valve
APD	Alarm Pocket Dosimeter
ARI	Alternative Rods Injection
BMU	Bundesministerium für Umwelt, Naturschutz und Reaktorsicherheit
BWR	Boiling Water Reactor
C/B	Control Building
CAMS	Containment Atmospheric Monitoring System
CCS	Containment Cooling System
CCSW	Containment Cooling Sea Water System
CDF	Core Damage Frequency
CFF	Containment Failure Frequency
CRD系	Control Rod Drive mechanism
CS	Core Spray System
D/DFP	Diesel-driven Fire Pump
DG	Diesel Generator
DGSW	Diesel Generator Sea Water System
DOE	United States Department of Energy
DSピット	Dryer Separator pit
D/W	Drywell
ECCS	Emergency Core Cooling System
EOC	Emergency Operation Center
EOP	Emergency Operating Procedures
EPZ	Emergency Planning Zone
ERC	Emergency Response Center
ERSS	Emergency Response Support System
FAO	Food and Agriculture Organization of the United Nations
FP	Fission Product
FP系	Fire Protection system

Abbreviation	English Term
FPC系	Fuel Pool Cooling system
HPCI	High Pressure Coolant Injection System
HPCS	High Pressure Core Spray System
HPCSDG	High Pressure Core Spray System Diesel Generator
IA系	Instrument Air system
IAEA	International Atomic Energy Agency
IC	Isolation Condenser
ICRP	International Commission on Radiological Protection
INES	The International Nuclear and Radiological Event Scale
IPE	Individual Plant Examination
IPEEE	Individual Plant Examination for External Events
JAEA	Japan Atomic Energy Agency
JAEA/NEAT	JAEA/Nuclear Emergency Assistance & Training Center
JAMSTEC	Japan Agency for Marine–Earth Science and Technology
JAXA	Japan Aerospace Exploration Agency
JNES	Japan Nuclear Energy Safety Organization
LPCI	Low Pressure Coolant Injection System
LPCS	Low Pressure Core Spray System
M	Magnitude
M/C	Metal–Clad Switch Gear
M/DFP	Motor–driven Fire Pump
MCC	Motor Control Center
MO弁	Motor Operated valve
MSIV	Main Steam Isolation Valve
MUWC系	Make–Up Water Condensate system
NEA	Nuclear Energy Agency
NRC	Nuclear Regulatory Commission
NUPEC	Nuclear Power Engineering Corporation
O.P.	Onahama Peil
O.P.	Onagawa Peil
OECD NEA	OECD Nuclear Energy Agency
P/C	Power Center
P/P	Physical Protection

Abbreviation	English Term
PAZ	Precautionary Action Zone
PRA	Probabilistic Risk Assessment
PSA	Probabilistic Safety Assessment
PSR	Periodic Safety Review
PWR	Pressurized Water Reactor
R/B	Reactor Building
RCIC	Reactor Core Isolation Cooling System
RHR	Residual Heat Removal System
RHRS	Residual Heat Removal Sea Water System
RPS	Reactor Protection System
RPT	Recirculation Pump Trip
RSK	Reaktor-Sicherheitskommission
RW/B	Radioactive Waste Disposal Building
S/C	Suppression Chamber
SA	Severe Accident
SARRY	Simplified Active Water Retrieve and Recovery System
SBO	Station Black Out
SCSIN	Service Central de Sûreté des Installations Nucléaires
SFP	Spent Fuel Pool
SGTS	Standby Gas Treatment System
SHC	Shutdown Cooling System
SLC	Standby Liquid Control System
SOP	Severe Accident Operating Procedures
SPDS	Safety Parameter Display System
SPEEDI	System for Prediction of Environmental Emergency Dose Information
SR弁	main Steam Relief valve
T.P.	Tokyo Peil
T/B	Turbine Building
TAF	Top of Active Fuel
UNSCEAR	United Nations Scientific Committee on the Effects of Atomic Radiation
WBC	Whole Body Counter
WHO	World Health Organization
WSPEEDI	Worldwide Version of System for Prediction of Environmental Emergency Dose Information